INDEX OF SHEETS

- 1. Cover Sheet
- 2.-3. Index of Sheets, General/Job Specific Notes, Commitments
- 4.-7. Summary of Quantities
- 8.-9. Typical Sections
- 10.-14. Schedules of Quantities
- 15. Alignment, Ties, and Benchmarks
- 16.-17. Plan Sheets
- 18.-19. Horizontal and Vertical Control
- 20. Removal Details
- 21. Right-of-Way Sheets
- 22. Pavement Marking Details
- 23. Lighting Detail
- 24.-36. Cross Sections
- 36.-51. District Standards

AVAILABILITY OF ELECTRONIC FILES

Micro Station and GEOPAK files of this project will be made available to the Contractor. If there is a conflict between the electronic files and the printed contract plans and documents, the printed contract plans and documents shall take precedence over the electronic files. The Contractor shall accept all risk associated with using the electronic files and shall hold the Department harmless for any errors or omissions in the electronic files and the data contained therein. Errors or delays resulting from the use of the electronic files by the Contractor shall not result in an extension of time for any interim or final completion date or shall not be considered cause for additional compensation. The Contractor shall not use, share, or distribute these electronic files except for the purpose of constructing this contract. Any claims by third parties due to use or errors shall be the responsibility of the Contractor. The Contractor shall include this disclaimer with the transfer of these electronic files to any other parties and shall include appropriate language binding them to similar responsibilities.

UTILITIES - LOCATIONS /INFORMATION ON PLANS

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown —— all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

ROUTE	OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
IL 9	25' LT.	811+45 TO 813+20	BURIED GAS	24" STORM SEWER	CAUTION
ORCHARDS RD	20' LT.	9+00	FIRE HYDRANT	CURB & DRIVEWAY	RÉLOCATE

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

The Contractor shall consult with the Engineer in regard to the exact length of the box/pipe culverts, storm sewers, and/or pipe drains required prior to ordering these items.

PROPERTY OWNER ACCESS REQUIREMENTS

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangements are made in writing by the Contractor with the property owners with a copy to the Engineer for short-term closures.

TEMPORARY MATERIAL REQUIREMENTS - UTILITY AND DRIVEWAY CROSSINGS

Incidental hot-mix asphalt surface shall be used for all temporary side road crossings. Aggregate surface course may be used for all driveway crossings except during winter shutdown in accordance with Article 107.09.

PAVEMENT STATIONING NUMBERS & PLACEMENT

The Contractor shall provide labor and materials required to imprint pavement station numbers in the finished surface of the pavement and/or overlay. The numbers shall be approximately 3/4 inch (20mm) wide, 5 inches (125 mm) high and 5/8 inch (15 mm) deep.

The pavement station numbers shall be installed as specified herein:

Interval - 200 feet (English stationing) or 100 meters (metric stationing)

Bottom of Numbers - 6 inches (150 mm) from the inside edge of the pavement marking

Location:

- * 2,3, & 5 Lane Pavements right edge of pavement in direction of increasing stations
- * Multi-Lane Divided Roadways outside edge of pavement in both directions
- * Ramps along baseline edge of pavement

Position - stations shall be placed so they can be read from the adjacent shoulder

Format – English (Metric) pavement stations shall use this format "XXX (XX + X00)" where X represents the pavement station

This work will not be paid for separately, but will be considered included in the cost of the associated pavement and/or overlay pay items.

COMMITMENTS

Commitments are not to be altered without the written approval of all parties to which the commitment was made.

SIGNING

Sign locations may vary from the stations shown on the plans in accordance with directions from the Engineer at the time of construction. Sign locations may be adjusted in the field to avoid any found utilities.

All wood post locations shall be verified with the Bureau of Operations, Traffic Section, before installation.

FILE NAME :	USER NAME + katubr	DESIGNED -	REVISED -					F.A.P. RTÉ.	SECTION	COUNTY TOT	AL SHEET ETS NO.
c:\temp\68b05\D4.68805\sht\cover.dgn		DRAWN -	REVISED ~	STATE OF ILLINOIS INDEX OF		INDEX OF SHEETS, GENERAL NOTES & COMMITMENTS		693	120N	TAZEWELL 51	1 Z
	PLOT SCALE . SB.8888 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	CONTRACT NO.	68805
Cofnult	PLOT DATE * 10/17/2013	DATE -	REVISED ~		SCALE: SHEET OF	F SHEETS STA,	TO STA.		ILLINOIS FED. A	D PROJECT	