

CHANGEABLE MESSAGE SIGN	
LOCATION	DAYS
Westbound Lanes	7
Eastbound Lanes	7
TOTAL	14

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DAY
Jobsite	2
TOTAL	2

CONSTRUCTION LAYOUT	
LOCATION	L SUM
Project Limits	1
TOTAL	1

PIPE CULVERTS TO BE CLEANED 24"	
LOCATION	FOOT
Jobsite	25
TOTAL	25

EARTHWORK TABLE		
LOCATION	EARTH EXCAVATION	FURNISHED EXCAVATION
	CU YD	CU YD
LT. STA 809+25 to 810+50	11.82	7.74*
LT. STA 812+00 to 813+25	89.57	120.99
TOTAL	101.39	120.99

* Paid as TOPSOIL FURNISH & PLACE 4"

EPOXY AND TEMPORARY PAVEMENT MARKINGS								RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL
LOCATION	LENGTH	EPOXY						EACH	EACH
		4" WHITE		4" YELLOW		24" WHITE STOP BAR	4" YELLOW CL		
		LT	RT	LT	RT	FOOT	FOOT		
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
County Highway 6									
4+60 TO 09+60	500	515	501	500	500	19	125	3	3
County Highway 6									
10+50 TO 15+50	500	501	505	500		18	125		
IL ROUTE 9									
805+45 TO 810+45	500	502	501		500	21	125	2	2
810+45 TO 811+86	141	112	69					1	1
811+86 TO 816+86	500	502	502	500		19	125	1	1
TOTALS		4210		2000		77	500	7	7

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\temp\68b05\04.68B05-sh-t-cover.dgn		DRAWN -	REVISED -
Default		CHECKED -	REVISED -
	PLOT DATE = 10/17/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. 809+25 TO STA. 812+75

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	120N	TAZEWELL	51	13
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B05	