

CONTRACT NO. 72501

2

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% FED 20% TOWNSHIP		
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP		
				0003 URBAN	0021				0028			
		URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN				
* Z0010688	CAMERA MOUNTING ASSEMBLY	EACH	4				4					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
* Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	2				1	1				
+ Z0070600	TRAINEES	HOURL	2,000	2,000								
Z0041500	PLUG EXISTING CULVERTS	EACH	5	5								
+ Z0070604	TRAINEES, TRAINING PROGRAM GRADUATE	HOURL	2,000	2,000								
MX602314	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2								
M6022047	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 15 FRAME AND LID	EACH	23	23								
MX602454	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1								
M6022099	MANHOLES, TYPE A, 2.4M DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1								
M6022272	MANHOLES, TYPE A, 2.7M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2								
MX602554	MANHOLES, TYPE A, 2.7M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1								
* MZ069961	STORM SEWER (WATER MAIN REQUIREMENTS) EQUIVALENT ROUND-SIZE ELLIPTICAL 600MM	METER	26.0	26.0								
* MZ069970	STORM SEWER (WATER MAIN REQUIREMENTS) EQUIVALENT ROUND-SIZE ELLIPTICAL 900MM	METER	24.5	24.5								
M3565280	BASE COURSE WIDENING 280 MM	SO M	13938	11,984						1,265	689	
MX606368	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-22.30 (SPECIAL)	METER	2477.8	2477.8								

2 12-30-13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY
SCALE: NONE
DATE: 06/2013
DRAWN BY: GE
CHECKED BY: FML

10
+0042 *SPECIALTY ITEM