

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | | | |
|----------|--|-------|----------------|--------------------------------|-------------------------------|-------------------------------|-------------------------------|
| | | | | 90% FED 10% STATE ROADWAY 0004 | 90% FED 10% STATE BRIDGE 0014 | 90% FED 10% STATE BRIDGE 0014 | 90% FED 10% STATE BRIDGE 0014 |
| | | | | NONE | S.N. 084-0150 | S.N. 084-0151 | S.N. 084-0154 |
| | | | | | | | |
| 50104650 | SLOPE WALL REMOVAL | SQ YD | 18 | | 10 | | 8 |
| 50104720 | REMOVAL OF EXISTING CONCRETE DECK | EACH | 2 | | 1 | | 1 |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 236 | 236 | | | |
| 50157300 | PROTECTIVE SHIELD | SQ YD | 1092 | | 596 | 343 | 496 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 175.6 | | 120.5 | | 55.1 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 1567.3 | | 810.9 | 54 | 756.4 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 2794 | | 1247 | | 1547 |
| 50300300 | PROTECTIVE COAT | SQ YD | 5069 | | 2465 | 26 | 2604 |
| 50400805 | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN. | FOOT | 370 | | 370 | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 26670 | | 12900 | | 13770 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 3366 | | 1656 | | 1710 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 384,540 | | 193120 | 4330 | 191410 |
| 50800515 | BAR SPLICERS | EACH | 518 | | 284 | 20 | 234 |
| 51100100 | SLOPE WALL 4 INCH | SQ YD | 18 | | 10 | | 8 |

4 12-30-13

* ITEM REQUIRES SPECIAL PROVISION

| | | | | | | | | | | | | |
|-------------------------------------|-----------------|-----------|---|------------------------------|-----------|----|--------|------------------|-----------|--|------------------|--------------|
| USER NAME : sporksgp | DESIGNED - BTM | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A.I. RTE. 1722 | SECTION * | COUNTY SANGAMON | TOTAL SHEETS 194 | SHEET NO. 64 |
| PLOT SCALE = 2.0000' / in. | DRAWN - BTM | REVISED - | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. | * (84-10-1RS-3, 84-10-2RS-4) BR.1 CONTRACT NO. 72C90 | | |
| PLOT DATE = Sep-06-2013 09:01:38 AM | CHECKED - JSA | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |
| | DATE - 12/19/12 | REVISED - | | 84-10-1, 2RS-3 & 84-10-2RS-4 | | | | | | | | |