

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N.084-0150	S.N. 084-0151	S.N. 084-0154
20200100	EARTH EXCAVATION	CU YD	514	514			
20400800	FURNISHED EXCAVATION	CU YD	573	573			
20700110	POROUS GRANULAR EMBANKMENT	TON	50		25		25
20800150	TRENCH BACKFILL	CU YD	46	46			
25000200	SEEDING, CLASS 2	ACRE	0.9	0.9			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2	2			
25100115	MULCH, METHOD 2	ACRE	0.9	0.9			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100			
28000400	PERIMETER EROSION BARRIER	FOOT	2754	2754			
28100107	STONE RIPRAP, CLASS A4	SQ YD	736	736			
28200200	FILTER FABRIC	SQ YD	736	736			

14

FILE NAME + c:\pvc_wrk\pvc\dot\porksg\ad022183\0672\290-shr-500.dgn	USER NAME + sparksgv	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES COMBINED- PARTS "A" & "B"				F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE + 100.0000 ' / in.	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	SANGAMON	194	3
	PLOT DATE + Sep-06-2013 10:42:40AM	DATE -	REVISED -										

* (84-10-185-3, 84-10-285-4)BR, I	CONTRACT NO. 72C90
ILLINOIS FED. AID PROJECT	