

PAVING SCHEDULE

LOCATION	STATION	TO	STATION	LENGTH (FT)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) (TON)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (TON)	HMA BASE COURSE, 10" (SQ YD)	HMA SHOULDERS (TON)	SHOULDER RUMBLE STRIP (FT)	AGGREGATE WEDGE SHOULDER, TYPE B (TON)	HMA SURFACE REMOVAL - BUTT JOINT (SY)	TEMPORARY RAMP (SY)
TR 420 RAMP A													
RAMP PVT	100+00.00	TO	103+02.30	302	0.10	34	23						
	103+02.30	TO	119+42.20	1,640	1.11	367	245					30	30
OUTSIDE SHLD	100+00.00 RT	TO	106+62.41 RT	662	0.28				82		45		
	106+62.41 RT	TO	119+42.20 RT	1,280	0.32				96		87		
INSIDE SHLD	103+02.30 LT	TO	106+62.41 LT	360	0.06				45				
	106+62.41 LT	TO	119+42.20 LT	1,280	0.22				64		154		
TR 420 RAMP B													
RAMP PVT	201+37.60	TO	217+49.60	1,612	1.09	361	241					30	30
	217+49.60	TO	224+99.80	750	0.25	84	56						
OUTSIDE SHLD	201+37.60 RT	TO	217+49.60 RT	1,612	0.41				120		110		
	217+49.60 RT	TO	224+99.80 RT	750	0.32				93		51		
INSIDE SHLD	200+75.00 LT	TO	217+49.60 LT	1,675	0.28				83		100		
	217+49.60 LT	TO	224+99.80 LT	750	0.13				37				
TR 420 RAMP C													
RAMP PVT	300+00.00	TO	303+02.50	303	0.10	34	23						
	303+02.50	TO	317+93.20	1,491	1.01	334	223					30	30
OUTSIDE SHLD	300+00.00 RT	TO	306+62.40 RT	662	0.28				82		45		
	306+62.40 RT	TO	317+93.20 RT	1,131	0.29				84		77		
INSIDE SHLD	303+02.50 LT	TO	306+62.40 LT	360	0.06				45				
	306+62.40 LT	TO	317+93.20 LT	1,131	0.19				56		136		
TR 420 RAMP D													
RAMP PVT	401+39.70	TO	415+84.40	1,445	0.98	162	216					30	30
	415+84.40	TO	423+40.60	756	0.26	85	56						
OUTSIDE SHLD	401+39.70 RT	TO	412+83.81 RT	1,144	0.29				85		103		
	412+83.81 RT	TO	423+40.60 RT	1,057	0.45				132		951		
INSIDE SHLD	401+39.70 LT	TO	411+77.20 LT	1,038	0.18				52		125		
	411+77.20 LT	TO	415+84.40 LT	407	0.07				20				
TOTALS =					107.7	39,723	14,926	652	15,073	99,498	11,288	2,813	1,529

USER NAME : sparksgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2,0000' / in.	DRAWN - BTM	REVISED -					J-72	*	SANGAMON	194	24
PLOT DATE = 5ep-06-2013 07:47:04AM	CHECKED - JSA	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			* (84-10-1)RS-3, (84-10-2)RS-4		CONTRACT NO. 72C90		
	DATE - 12/19/12	REVISED -					ILLINOIS FED. AID PROJECT				