

EXIST. CURVE 3, RAMP D
 PI STA. = 18+12.58
 Δ = 5° 17' 02" (LT)
 D = 0° 30' 00"
 R = 11,459.16'
 T = 528.77'
 L = 1,056.78'
 E = 12.19'
 e = NA
 T.R. = NA
 S.E. RUN = NA
 P.C. STA. = 12+83.81
 P.T. STA. = 23+40.59


EXIST. CURVE 2, RAMP D
 PI STA. = 410+12.75
 Δ = 42° 45' 38" (RT)
 D = 7° 30' 00"
 R = 763.94'
 T = 299.08'
 L = 570.14'
 E = 56.46'
 e = 8.0%
 T.R. = 48.00'
 S.E. RUN = 256.00'
 P.C. STA. = 407+13.67
 P.T. STA. = 412+83.81

EXIST. CURVE C6 (I-72)
 PI STA. = 256+98.47
 Δ = 9° 39' 43" (RT)
 D = 0° 30' 00"
 R = 11,459.16'
 T = 968.49'
 L = 1,932.39'
 E = 40.85'
 e = 1.67%
 T.R. = 67.50'
 S.E. RUN = 75.00'
 P.C. STA. = 247+29.98
 P.T. STA. = 266+62.37

EXIST. CURVE 1, RAMP A
 PI STA. = 103+31.30
 Δ = 3° 18' 43" (RT)
 D = 0° 30' 00"
 R = 11,459.16'
 T = 331.30'
 L = 662.41'
 E = 4.79'
 e = NA
 T.R. = NA
 S.E. RUN = NA
 P.C. STA. = 100+00.00
 P.T. STA. = 106+62.41

EXIST. CURVE 2, RAMP A
 PI STA. = 109+67.86
 Δ = 43° 35' 13" (RT)
 D = 7° 30' 00"
 R = 763.94'
 T = 305.45'
 L = 581.16'
 E = 58.80'
 e = 8.0%
 T.R. = 48.00'
 S.E. RUN = 256.00'
 P.C. STA. = 106+62.41
 P.T. STA. = 112+43.56

- PAVEMENT MARKING LEGEND
- ① PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 5" (30' SKIP, 10' DASH)
 - ② PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID YELLOW)
 - ③ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID WHITE)
 - ④ PR URETHANE PAVEMENT MARKING, LINE 6" (SOLID WHITE)
 - ⑤ PR URETHANE PAVEMENT MARKING, LINE 6" (6' SKIP, 2' DASH)
 - ⑥ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 8" (SOLID WHITE)
 - ⑦ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID WHITE)
 - ⑧ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 24" (SOLID WHITE)
 - ⑨ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LETTERS & SYMBOLS (SOLID WHITE)
 - ▽ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, WHITE
 - ◀ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, AMBER



USER NAME = sparkegw	DESIGNED - BTM	REVISED -
PLOT SCALE = 1/8" = 100'	DRAWN - BTM	REVISED -
PLOT DATE = Sep-06-2013 09:20:49AM	CHECKED - JSA	REVISED -
	DATE - 12/19/12	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PLAN SHEETS				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1-72	*	SANGAMON	194	46
* (84-10-1)RS-3, (84-10-2)RS-4 CONTRACT NO. 72C90				
ILLINOIS FED. AID PROJECT				