

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY 0004 NONE	90% FED 10% STATE BRIDGE 0014	90% FED 10% STATE BRIDGE 0014	90% FED 10% STATE BRIDGE 0014
					S.N. 084-0150	S.N. 084-0151	S.N. 084-0154
50104650	SLOPE WALL REMOVAL	SQ YD	18		10		8
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2		1		1
50105220	PIPE CULVERT REMOVAL	FOOT	236	236			
50157300	PROTECTIVE SHIELD	SQ YD	1405		596	313	496
50300225	CONCRETE STRUCTURES	CU YD	175.6		120.5		55.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1572.7		810.9	5.4	756.4
50300260	BRIDGE DECK GROOVING	SQ YD	2794		1247		1547
50300300	PROTECTIVE COAT	SQ YD	5095		2465	26	2604
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	370		370		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	26670		12900		13770
50500505	STUD SHEAR CONNECTORS	EACH	3366		1656		1710
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	385860		193120	1330	191410
50800515	BAR SPLICERS	EACH	538		284	20	234
51100100	SLOPE WALL 4 INCH	SQ YD	18		10		8

\* ITEM REQUIRES SPECIAL PROVISION

USER NAME = sparkgw	DESIGNED - BTM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE. 1722	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 194	SHEET NO. 64
PLOT SCALE = 2.0000' / 1" =	DRAWN - BTM	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	* (84-10-1RS-3,84-10-2RS-4)BR.1 CONTRACT NO. 72C90			
PLOT DATE = Sep-95-2813 09:01:38AM	CHECKED - JSA	REVISED -		[ILLINOIS] FED. AID PROJECT								
DATE - 12/19/12	REVISED -			84-10-1,2RS-3 & 84-10-2RS-4								