

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				90% FED 10% STATE ROADWAY 0004 NONE	90% FED 10% STATE BRIDGE 0014 S.N. 084-0150	90% FED 10% STATE BRIDGE 0014 S.N. 084-0151	90% FED 10% STATE BRIDGE 0014 S.N. 084-0154				
				X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
				<b>X7200201</b>	<b>WIDTH RESTRICTION SIGNING</b>	L SUM	1	1			
X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	10717	10717							
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	354	354							
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	54		27		27				
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	13700		6800		6900				
Z0003615	REMOVAL OF EXISTING CONCRETE I-BEAM	EACH	14		14						
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	173		145		28				
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	20			20					
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10			10					
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	50			50					
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	8		4		4				
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2							
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	2		1		1				
Z0041500	PLUG EXISTING CULVERTS	EACH	8	8							
Z0053700	RESETTING SURVEY MONUMENTS	EACH	1	1							

△

110

\* ITEM REQUIRES SPECIAL PROVISION

USER NAME : sparksg	DESIGNED - BTM	REVISED - △ 10/28/13
PLOT SCALE : 2.0000' / in.	DRAWN - BTM	REVISED -
PLOT DATE : Sep-06-2013 09:04:05AM	CHECKED - JSA	REVISED -
	DATE - 12/19/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1722	*	SANGAMON	194	69
* (84-10-IRS-3,84-10-2RS-4)BR.1 CONTRACT NO. 72C90				
[ILLINOIS] FED. AID PROJECT				