

SEEDING SCHEDULE										
LOCATION	STATION	TO	STATION	AREA (SQ FT)	SEEDING, CL 2 (ACRE)	MULCH, METHOD 2 (ACRE)	AGRICULT GROUND LIMESTONE (TON)	PHOS FERT NUTR (POUND)	POT FERT NUTR (POUND)	NITROGEN FERT NUTR (POUND)
MECHANICSBURG RD. MAINLINE										
	88+50.00	TO	89+00.00	100	0.00	0.00	0.00	0	0	0
	89+00.00	TO	89+50.00	142	0.00	0.00	0.01	0	0	0
	89+50.00	TO	90+00.00	117	0.00	0.00	0.01	0	0	0
	90+00.00	TO	90+50.00	118	0.00	0.00	0.01	0	0	0
	90+50.00	TO	91+00.00	107	0.00	0.00	0.00	0	0	0
	91+00.00	TO	91+50.00	202	0.00	0.00	0.01	0	0	0
	91+50.00	TO	92+00.00	474	0.01	0.01	0.02	1	1	1
	92+00.00	TO	92+50.00	689	0.02	0.02	0.03	1	1	1
	92+50.00	TO	93+00.00	841	0.02	0.02	0.04	2	2	2
	93+00.00	TO	93+50.00	1,194	0.03	0.03	0.05	2	2	2
	93+50.00	TO	94+00.00	300	0.01	0.01	0.01	1	1	1
	94+00.00	TO	94+50.00	1,286	0.03	0.03	0.06	3	3	3
	94+50.00	TO	95+00.00	531	0.01	0.01	0.02	1	1	1
	95+00.00	TO	95+50.00	307	0.01	0.01	0.01	1	1	1
	95+50.00	TO	96+00.00	325	0.01	0.01	0.01	1	1	1
	96+00.00	TO	96+50.00	437	0.01	0.01	0.02	1	1	1
	96+50.00	TO	97+00.00	564	0.01	0.01	0.03	1	1	1
	97+00.00	TO	97+50.00	581	0.01	0.01	0.03	1	1	1
	97+50.00	TO	98+00.00	622	0.01	0.01	0.03	1	1	1
	98+00.00	TO	98+37.00	3,277	0.08	0.08	0.15	7	7	7
	101+79.00	TO	102+00.00	940	0.02	0.02	0.04	2	2	2
	102+00.00	TO	102+50.00	3,986	0.09	0.09	0.18	8	8	8
	102+50.00	TO	103+00.00	748	0.02	0.02	0.03	2	2	2
	103+00.00	TO	103+50.00	644	0.01	0.01	0.03	1	1	1
	103+50.00	TO	104+00.00	546	0.01	0.01	0.03	1	1	1
	104+00.00	TO	104+50.00	378	0.01	0.01	0.02	1	1	1
	104+50.00	TO	105+00.00	269	0.01	0.01	0.01	1	1	1
	105+00.00	TO	105+50.00	264	0.01	0.01	0.01	1	1	1
	105+50.00	TO	106+00.00	70	0.00	0.00	0.00	0	0	0
	106+00.00	TO	106+50.00							
	106+50.00	TO	107+00.00	221	0.01	0.01	0.01	0	0	0
	107+00.00	TO	107+50.00	234	0.01	0.01	0.01	0	0	0
	107+50.00	TO	108+00.00	240	0.01	0.01	0.01	0	0	0
	108+00.00	TO	108+50.00	216	0.00	0.00	0.01	0	0	0
	108+50.00	TO	109+00.00	167	0.00	0.00	0.01	0	0	0
	109+00.00	TO	109+50.00	128	0.00	0.00	0.01	0	0	0
	109+50.00	TO	110+00.00	101	0.00	0.00	0.00	0	0	0
	110+00.00	TO	110+50.00	69	0.00	0.00	0.00	0	0	0
	110+50.00	TO	111+00.00	140	0.00	0.00	0.01	0	0	0
	111+00.00	TO	111+50.00	162	0.00	0.00	0.01	0	0	0
	111+50.00	TO	112+00.00	122	0.00	0.00	0.01	0	0	0
	112+00.00	TO	112+26.46	28	0.00	0.00	0.00	0	0	0

SEEDING SCHEDULE										
LOCATION	STATION	TO	STATION	AREA (SQ FT)	SEEDING, CL 2 (ACRE)	MULCH, METHOD 2 (ACRE)	AGRICULT GROUND LIMESTONE (TON)	PHOS FERT NUTR (POUND)	POT FERT NUTR (POUND)	NITROGEN FERT NUTR (POUND)
TR 420 MAINLINE										
	291+50.00	TO	292+00.00	93	0.002	0.002	0.004	0	0	0
	292+00.00	TO	292+50.00	166	0.00	0.00	0.01	0	0	0
	292+50.00	TO	293+00.00	194	0.00	0.00	0.01	0	0	0
	293+00.00	TO	293+50.00	166	0.00	0.00	0.01	0	0	0
	293+50.00	TO	294+00.00	1,252	0.03	0.03	0.06	3	3	3
	294+00.00	TO	294+50.00	817	0.02	0.02	0.04	2	2	2
	294+50.00	TO	295+00.00	876	0.02	0.02	0.04	2	2	2
	295+00.00	TO	295+50.00	437	0.01	0.01	0.02	1	1	1
	295+50.00	TO	296+00.00	355	0.01	0.01	0.02	1	1	1
	296+00.00	TO	296+50.00	635	0.01	0.01	0.03	1	1	1
	296+50.00	TO	297+00.00	728	0.02	0.02	0.03	2	2	2
	297+00.00	TO	297+50.00	654	0.02	0.02	0.03	1	1	1
	297+50.00	TO	298+00.00	562	0.01	0.01	0.03	1	1	1
	298+00.00	TO	298+50.00	3,967	0.09	0.09	0.18	8	8	8
	301+50.00	TO	302+00.00	3,915	0.09	0.09	0.18	8	8	8
	302+00.00	TO	302+50.00	523	0.01	0.01	0.02	1	1	1
	302+50.00	TO	303+00.00	633	0.01	0.01	0.03	1	1	1
	303+00.00	TO	303+50.00	731	0.02	0.02	0.03	2	2	2
	303+50.00	TO	304+00.00	710	0.02	0.02	0.03	1	1	1
	304+00.00	TO	304+50.00	643	0.01	0.01	0.03	1	1	1
	304+50.00	TO	305+00.00	538	0.01	0.01	0.02	1	1	1
	305+00.00	TO	305+50.00	347	0.01	0.01	0.02	1	1	1
	305+50.00	TO	306+00.00	196	0.00	0.00	0.01	0	0	0
	306+00.00	TO	306+50.00	194	0.004	0.004	0.01	0.4	0.4	0.4
	306+50.00	TO	307+00.00	641	0.01	0.01	0.03	1	1	1
	307+00.00	TO	307+50.00	576	0.01	0.01	0.03	1	1	1
	307+50.00	TO	308+00.00	474	0.011	0.011	0.022	1.0	1.0	1.0
	308+00.00	TO	308+50.00	198	0.005	0.005	0.009	0.4	0.4	0.4
TOTALS =					0.9	0.9	2.0	90	90	90

USER NAME = sparkgw PLOT SCALE = 2.0000' / in. PLOT DATE = Sep-06-2013 09:10:46AM	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE. 1772	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 194	SHEET NO. 82
	DRAWN - BTM	REVISED -						* (84-10-1RS-3,84-10-2RS-4)BR,1		CONTRACT NO. 72C90		
	CHECKED - JSA	REVISED -		SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
	DATE - 12/19/12	REVISED -						(84-10-1,2)RS-3 & (84-10-2)RS-4				