



PLAN

LEGEND

- Slope wall, 4"
- sf square feet

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Slope Wall Removal	Sq. Yd.	8
Slope Wall, 4"	Sq. Yd.	8
Controlled Low Strength Material	Cu. Yd.	4

Notes:

Slope wall shall be reinforced with welded wire fabric, 6"x 6" - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft. Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Slope wall Repair.

Existing and new welded wire fabric must be lapped at least 6".

Repair of the existing slope walls shall include but may not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

FILE NAME = TR420 over FAI-72.dgn	USER NAME =	DESIGNED - SAL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SLOPEWALL REPAIR DETAILS OVERPASS ROAD (TR-420) OVER F.A.I.-72 - S.N. 084-0154	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED - MTH	REVISED -			72	*	SANGAMON	194	170	
		DRAWN - TJW	REVISED -			* (84-10-1RS-3, 84-10-2RS-RIBR,1					
		CHECKED - MTH	REVISED -			FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT					
				SHEET NO. 23 OF 25 SHEETS							