

PAVEMENT MARKING

PAVEMENT MARKING LOCATIONS (PLAN SHEETS, MATCH LINE TO MATCH LINE)	STATION TO STATION DISTANCE (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 5"		THPL PVMT MK - LINE 6"	THPL PVMT MK - LINE 8"		THPL PVMT MK - LINE 12"		PREF PL PVMT MK TY B - INLAID - LINE 24"		PREF PL PVMT MK TY B INLAID L&S WHITE		RAISED REFLECTIVE PAVEMENT MARKERS 78100100			RAISED REFLECTIVE PAVEMENT MARKER REMOVAL 78300200
		78000300		78000400	78000500		78000600		78004280		78004200		ONE-WAY CRYSTAL	ONE-WAY AMBER	TWO-WAY AMBER	78300200
		WHITE (FOOT)	YELLOW (FOOT)	(FOOT)	WHITE (FOOT)	YELLOW (FOOT)	WHITE (FOOT)	YELLOW (FOOT)	WHITE (FOOT)	YELLOW (FOOT)	(FOOT)	(SQ FT)	(EACH)	(EACH)	(EACH)	(EACH)
WABASH AVENUE																
492+79.38	TO	496+84.77	405.39	170.0	8,088.0	273.0	710.0	337.0	81.0	194.0	156.0	62		18		
496+84.77	TO	502+39.77	555.00	280.0	1,111.0	207.0		187.0	37.0		93.6	43		28		
502+39.77	TO	507+94.77	555.00	290.0	722.0	747.0	885.0	80.0	334.0	14.0	234.0	76	4	4		
507+94.77	TO	511+60.00	365.23	178.0	754.0	760.0						32				
511+60.00	TO	511+70.00	10.00	7.0		14.0										
PROJECT OMISSION: 511+70 TO 515+00																
515+00.00	TO	515+10.00	10.00		20.0	30.0										
515+10.00	TO	519+04.77	394.77	210.0	953.0	1,216.0					202.8	42	4			
519+04.77	TO	521+74.15	269.38	80.0	792.0	660.0		16.0	13.5	144.0	62.4	16	8			
STA. EQUATION: 521+74.15 BACK = 521+79.92 AHEAD																
521+79.92	TO	524+65.54	285.62	140.0	618.0	183.0					31.2	11		2		
524+65.54	TO	530+20.54	555.00	230.0	1,244.0	1,000.0				129.0	218.4	32	16			
530+20.54	TO	535+75.54	555.00	280.0	1,010.0	753.0				24.0	109.2	29				
535+75.54	TO	541+30.54	555.00	265.0	998.0	209.0				17.0	15.6	16				
541+30.54	TO	546+85.54	555.00	285.0	1,188.0	272.0		10.0	13.0		62.4	26	2			
546+85.54	TO	552+40.54	555.00	240.0	1,615.0	961.0		78.0	81.0	119.0	171.6	30	12			
552+40.54	TO	554+99.18	258.64	130.0	514.0	155.0		15.0			31.2	11				
STA. EQUATION: 554+99.18 BACK = 555+00.00 AHEAD																
555+00.00	TO	557+96.37	296.37	150.0	592.0	77.0						9				
557+96.37	TO	563+51.37	555.00	220.0	1,222.0	990.0	105.0	67.3	6.0	140.0	202.8	41	10			
563+51.37	TO	569+06.37	555.00	195.0	983.0	2,080.0	782.0	154.0		178.0	296.4	72				
569+06.37	TO	574+61.37	555.00	270.0	1,041.0	1,227.0	180.0	31.7		72.0	124.8	45				
574+61.37	TO	577+99.99	338.62	160.0	656.0	136.0				20.0	31.2	8		10		
STA. EQUATION: 577+99.99 BACK = 578+00.00 AHEAD																
578+00.00	TO	580+16.37	216.37	110.0	442.0	113.0					62.4	9		12		
580+16.37	TO	585+71.37	555.00	280.0	1,329.0	229.0					124.8	17		28		
585+71.37	TO	591+26.37	555.00	240.0	1,060.0	262.0				91.0	124.8	17		26		
591+26.37	TO	596+81.37	555.00	270.0	1,171.0	113.0				16.0	109.2	16		26		
596+81.37	TO	602+36.37	555.00	280.0	1,390.0						93.6	14		28		
602+36.37	TO	603+08.51	72.14	40.0	144.0	21.0					15.6	3		4		
STA. EQUATION: 603+08.51 BACK = 83+28.31 AHEAD																
83+28.31	TO	85+90.00	261.69	80.0	582.0	428.0				125.0	78.0	8		8		
SUBTOTALS =			10954.22	5,080.0	30,239.0	13,116.0	2,662.0	80.0	1,230.0	322.5	1,461.0	2,652.0	685	58	192	935
OVERALL TOTALS =				35,319.0	13,116.0	2,742.0	1,552.5	1,461.0	2,652.0	685	935	192	935			

SHORT TERM PAVMENT MARKING / WORK ZONE PAVEMENT MARKING REMOVAL			
APPLICATIONS	SHORT TERM PAVEMENT MARKING 70300100		WORK ZONE PAVEMENT MARKING REMOVAL (5" LINE WIDTH) 70301000 (SQUARE FOOT)
	WHITE (FOOT)	YELLOW (FOOT)	
FIRST APPLICATION	1,200	2,332	
SECOND APPLICATION	1,200	2,332	1,472
SUBTOTALS=	2,400	4,664	1,472
OVERALL TOTALS=	7,064		1,472

LOCATION OF SIDEWALK	COMBINATION CURB AND GUTTER REMOVAL 44000500 (FOOT)	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 60605000 (FOOT)	SIDEWALK REMOVAL (AREA BY CADD) 44000600 (SQUARE FOOT)	PORTLAND CEMENT CONCRETE SIDEWALK 4" 42400100 (SQUARE FOOT)	DETECTABLE WARNINGS 42400800 (SQ FT)
	WABASH AVENUE				
WHITE OAKS MALL, EAST ENTRANCE	28.5	28.5	99.8	99.8	36.5
COLONY WEST ENTRANCE	29.3	29.3	280.4	266.9	40.0
SPRINGFIELD CLINIC ENTRANCE	28.4	28.4	165.5	165.5	38.3
MONTVALE DRIVE	42.4	42.4	504.2	461.8	48.1
KIRKLEY LANE	29.2	29.2	403.3	524.3	38.0
ROBINHOOD LANE (NORTH OF WABASH AVE.)	26.5	26.5	126.2	125.5	32.3
ROBINHOOD LANE (SOUTH OF WABASH AVE.)	74.0	74.0	591.2	610.2	50.8
CHATHAM ROAD (NORTH OF WABASH AVE.)			250.8	250.8	72.6
CHATHAM ROAD (SOUTH OF WABASH AVE.)			99.7	99.7	64.0
PARK STREET (NORTH OF WABASH AVE.)	18.5	18.5		136.0	20.0
PARK STREET (SOUTH OF WABASH AVE.)	13.5	13.5		693.2	27.0
TOTALS=	290.3	290.3	2,521.1	3,433.7	447.6

CHANGEABLE MESSAGE SIGNS	
LOCATION OF SIGN	CHANGEABLE MESSAGE BOARD 70106800 (CAL MONTH)
JUST WEST OF KOKE MILL & WABASH INTERSECTION, EASTBOUND LANES	2.0
VETERANS & WABASH INTERSECTION, NORTHBOUND LANES	2.0
VETERANS & WABASH INTERSECTION, SOUTHBOUND LANES	2.0
CHATHAM ROAD & WABASH INTERSECTION, NORTHBOUND LANES	2.0
CHATHAM ROAD & WABASH INTERSECTION, SOUTHBOUND LANES	2.0
MAC ARTHUR & WABASH / STANFORD INTERSECTION, WESTBOUND LANES	2.0
MAC ARTHUR & WABASH / STANFORD INTERSECTION, NORTHBOUND LANES	2.0
MAC ARTHUR & WABASH / STANFORD INTERSECTION, SOUTHBOUND LANES	2.0
TOTALS =	16.0