## INDEX OF SHEETS

- 1. COVER
- 2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
- 3. SUMMARY OF QUANTITIES
- 4. LOCATION MAP
- 5. TYPICAL SECTIONS
- 6. SCHEDULES

## HIGHWAY STANDARDS

701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT

701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM EDGE OF PAVEMENT

701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY

701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

701306-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH

701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY

701901-03 TRAFFIC CONTROL DEVICES

780001-04 TYPICAL PAVEMENT MARKINGS

## GENERAL NOTES

- 1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 2.NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
- 3. THE AGGREGATE GRADATION FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CA-16 OR CA-20.
- 4. AGGREGATE FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CRUSHED LIMESTONE.
- 5. SHORT-TERM PAVEMENT MARKING SHALL BE PAINT TAPE WILL NOT BE ALLOWED.
- 6. PERMANENT PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL 10 DAYS AFTER THE AGGREGATE HAS BEEN APPLIED.
- 7. ADDITIONAL BROOMING (UP TO 4 TIMES) SHALL BE REQUIRED AT THE DISCRETION OF THE ENGINEER. INCLUDING THE DAY OF PERMANENT PAVEMENT MARKING.
- 8. THE CONTRACTOR SHALL GIVE IDOT OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR IDOT TO COMPLETE PATCHING.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6						
EXAMINED	Oy 7	20 / 3				
Bul B	ENGII	NEER OF OPERATIONS				
EXAMINED		20 13				
0	<del>-</del>	CT IMPLEMENTATION				
EXAMINED	9-16  RM:/ ENGINEER OF PROG	20 13 RAM DEVELOPMENT				

FILE NAME .	USER NAME * sharptd	DESIGNED -	REVISED -		INDEX OF SHEETS, HIGHWAY STANDARDS	F.A.S. SECTION	COUNTY TOTAL SHEET
et\pw.work\pwidot\aherptd\d8351583\IND-5	18-SIGN.dgn	ORAWN +	REVISED -	STATE OF ILLINOIS	AND GENERAL NOTES	636 (2,3) 0	CHRISTIAN 6 2
1	PLOT SEALE * 1.0000 '/ in.	CHECKED ~	REVISED -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 72G33
Default	PLOT DATE + Aug-21-2813 85:14:22AM	DATE -	REVISED -		SCALE, SHEET 1 OF 1 SHEETS STA. TO STA.	ILLINOIS FEO.	AID PROJECT