SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FEDERAL 20% STATE ROADWAY 0004	STRUCTURES 0011	
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	217	217		
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	179	179		
	20200100	EARTH EXCAVATION	CU YD	2065	2065		
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	15.2	15.2		
	20400800	FURNISHED EXCAVATION	CU YD	579	579		
	20800150	TRENCH BACKFILL	CU YD	72	72		
*	25100630	EROSION CONTROL BLANKET	SQ YD	2029	2029		
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	126	126		
	28000305	TEMPORARY DITCH CHECKS	FOOT	72	72		
	28000400	PERIMETER EROSION BARRIER	FOOT	1363	1363		
	28000500	INLET AND PIPE PROTECTION	EACH	9	9		
	28001000	AGGREGATE (EROSION CONTROL)	TON	41	41		
	28100107	STONE RIPRAP, CLASS A4	SQ YD	2188	1338	850	

13

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FEDERAL 20% STATE ROADWAY 0004	STRUCTURES 0011	
28200200	FILTER FABRIC	SQ YD	2188	1338	850	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	106	106		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	31	31		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	169	169		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	95	95		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	298	298		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	141	141		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	56	56		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1761	1761		
44000100	PAVEMENT REMOVAL	SQ YD	309	309		
44000400	GUTTER REMOVAL	FOOT	200	200		
44000600	SIDEWALK REMOVAL	SQ FT	1528	1528		

12

* SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\staffenmk\d0122333\D774228-sht-500.dgn	USER NAME = staffenmk	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.2000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 10/17/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A | SHEET 1 OF 4 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(103BJB-1)	WABASH	53	3
		CONTRACT NO. 74220		
	ILLINOIS FED. AID PROJECT			