

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4" WHITE	TEMPORARY PAVEMENT MARKING - LINE 4" WHITE YELLOW	TEMPORARY PAVEMENT MARKING - LINE 6" WHITE	TEMPORARY PAVEMENT MARKING - LINE 12" YELLOW	TEMPORARY PAVEMENT MARKING - LINE 24" WHITE	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	EACH
450+83.00 TO 452+50.00	167.0	0.0	0.0	0.0	0.0	24.0	0.0	0.0	0.0	0.0	0.0	24.0	0.0	32.0	5.3	0.0
452+50.00 TO 469+91.00	1741.0	3482.0	435.3	0.0	0.0	0.0	0.0	3482.0	435.3	0.0	0.0	0.0	0.0	352.0	58.7	22.0
469+91.00 TO 477+01.00	710.0	1420.0	887.5	0.0	0.0	0.0	0.0	1420.0	887.5	0.0	0.0	0.0	0.0	144.0	24.0	9.0
477+01.00 TO 477+30.89	29.9	59.8	59.8	0.0	0.0	0.0	0.0	59.8	59.8	0.0	0.0	0.0	0.0	8.0	1.3	0.0
477+30.89 = 477+42.92	12.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
477+42.92 TO 481+03.00	360.1	720.2	720.2	0.0	0.0	0.0	0.0	720.2	720.2	0.0	0.0	0.0	0.0	72.0	12.0	5.0
481+03.00 TO 486+00.00	497.0	994.0	994.0	0.0	247.8	0.0	0.0	994.0	994.0	0.0	247.8	0.0	0.0	96.0	16.0	24.9
486+00.00 TO 488+50.00	250.0	300.0	394.0	115.0	21.0	0.0	31.2	300.0	394.0	115.0	21.0	0.0	31.2	96.0	16.0	20.0
TOTAL:	3767	6975.94	3490.69	115	268.8	24	31.2	6975.94	3490.69	115	268.8	24	31.2	800.0	133.3	81

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TEMPORARY RAMP
	FOOT	FOOT	SQ YD	SQ YD	GALLON	TON	TON	SQ YD
450+83.00 TO 477+01.00	2618.0	22.0	6400	6400	640	13	538	74
477+30.89 BK = 477+42.92 AH								
477+01.00 TO 479+31.00	230.0							
479+31.00 TO 481+03.00	172.0	22.0	420	420	42	1	35	12
481+03.00 TO 486+00.00	497.0	30.0	1657	1657	166	3	139	
486+00.00 TO 488+50.00	250.0	38.0	1056	1056	106	2	89	21
TOTALS			9532	9532	953	19	801	108