

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

URBAN

90 / 10 FED / STATE

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						SIGNS	100% STATE
				ROADWAY 0004	SN 060-0218 SN 060-0219 0014	SN 060-0220 SN 060-0221 0014	SN 060-0222 SN 060-0242 0014	SN 060-0224 0014	SN 060-0243 0014		
50800105	REINFORCEMENT BARS	POUND	2380	2380							
50800515	BAR SPLICERS	EACH	114			44	33	26	11		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	583			275	183	85	40		
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	7008		5030		1978				
58700300	CONCRETE SEALER	SO FT	5939		5939						
X5870015	BRIDGE DECK CONCRETE SEALER	SQ FT	119046			63747	26036	15533	14530		
59000200	EPOXY CRACK INJECTION	FOOT	12						12		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	4					4			
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	16	16							
60100073	SHOULDER REMOVAL AND REPLACEMENT 10"	FOOT	80	80							
60100945	PIPE DRAINS 12"	FOOT	290	290							
60107600	PIPE UNDERDRAINS 4"	FOOT	3200	3200							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	862	862							
60500060	REMOVING INLETS	EACH	29	29							
60602500	CONCRETE GUTTER, TYPE A	FOOT	278	278							
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	4	4							

14