



DECK PLAN VIEW

LEGEND

- Concrete Removal for Joint Replacement (See Sheet 7,8)
- Deck Slab Repair (Full Depth, Type I)

| Patch No. | Patch Depth | Station | Length (ft) | Width (ft) | Quantity (sq. yd.) |
|-----------|-------------|------------|-------------|------------|--------------------|
| 1 | Full | 1528+87.62 | 1 | 1 | 0.11 |
| 2 | Full | 1529+25.62 | 1 | 1 | 0.11 |

BILL OF MATERIAL

| Item | Unit | Total |
|--|---------|-------|
| *Deck Slab Repair (Full Depth, Type I) | Sq. Yd. | 2.0 |

*Additional Deck Slab Repair (Full Depth, Type I) quantity has been included in the event full depth patches are identified during construction. Location not shown.

4/15/2013 4:15:21 PM g:\s12\0001\Bridges\CAD\Drawings\0220-0221\0600221-76F10-06-Deck Patching Plan.dgn

FILE NAME = *FILES*



| | | |
|-----------------------|----------------|-----------|
| USER NAME = sdogann | DESIGNED - SDG | REVISED - |
| PLOT SCALE = *SCALE* | CHECKED - FAS | REVISED - |
| PLOT DATE = 4/15/2013 | DRAWN - JK | REVISED - |
| | CHECKED - SDG | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK PATCHING PLAN
STRUCTURE NO. 060-0221 NB

SHEET NO. 6 OF 19 SHEETS

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------------|---------|--------------------|-----------|
| 255 | 60-(8,9) RS-1 | MADISON | 206 | 156 |
| ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 76F10 | |