



DECK PLAN VIEW

LEGEND

- Concrete Removal for Joint Replacement (See Sheet 8,9)
- Deck Slab Repair (Partial Depth)

BILL OF MATERIAL

Item	Unit	Total
Deck Slab Repair (Partial Depth)	Sq. Yd.	22.4
*Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	2.0

* Additional Deck Slab Repair (Full Depth, Type I) quantity has been included in the event full depth patches are identified during construction. Location not shown.

NOTES:

1. The Contractor shall use extreme care during concrete removal so as not to damage the existing 2 1/2" precast, prestressed stay-in-place forms.

Patch No.	Patch Depth	Station	Length (ft)	Width (ft)	Quantity (sq. yd.)
1	Partial	1617+01.55	3	3	1.00
2	Partial	1617+33.33	3	3	1.00
3	Partial	1618+06.55	2	2	0.44
4	Partial	1618+24.55	3	3	1.00
5	Partial	1618+27.55	6	6	4.00
6	Partial	1618+29.41	3	3	1.00
7	Partial	1618+33.55	12	6	8.00
8	Partial	1618+36.55	3	3	1.00
9	Partial	1618+39.55	3	3	1.00
10	Partial	1618+41.41	6	6	4.00

4/16/2013 12:00:00 Bridge\CAD\sheets\Bridg 0222-0242\0600222-76F10-08-Deck Patching Plan.dgn \$TIME\$

FILE NAME = \$FILES\$



USER NAME = sdogenn	DESIGNED - SDG	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED - FAS	REVISED -
PLOT DATE = 4/16/2013	DRAWN - DMG	REVISED -
	CHECKED - SDG	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK PATCHING PLAN
STRUCTURE NO. 060-0222 SB

SHEET NO. 8 OF 14 SHEETS

F.A.I. RTE. 255	SECTION 60-(8,9) RS-1	COUNTY MADISON	TOTAL SHEETS 206	SHEET NO. 177
			CONTRACT NO. 76F10	
ILLINOIS FED. AID PROJECT				