

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005	0021	TRAFFIC SIG.
CODE NO	ITEM	UNIT	80% FED 20% STATE	50% STATE 50% CITY	80% FED 13.3% STATE 6.7% CITY	
20400800	FURNISHED EXCAVATION	CU YD	162			
28100107	STONE RIPRAP, CLASS A4	SO YD	653			
28200200	FILTER FABRIC	SO YD	653			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	11			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33.4	32.3	1.1	
40600300	AGGREGATE (PRIME COAT)	TON	199	191	8	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2168	1947	221	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1387	1387		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	711	711		
40600990	TEMPORARY RAMP	SO YD	1042	1042		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	7189	6968	221	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	139	139		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	47414	47414		

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
					0005	0021	TRAFFIC SIG.
CODE NO	ITEM	UNIT	80% FED 20% STATE	50% STATE 50% CITY	80% FED 13.3% STATE 6.7% CITY		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	966				
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	19371				
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SO YD	7163	4537	2626		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	21	21			
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	30	30			
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	68	68			
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	32	32			
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	505	505			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	48024	48024			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1172	1172			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	746	746			
50105220	PIPE CULVERT REMOVAL	FOOT	76	76			
54215559	METAL END SECTIONS 24"	EACH	2	2			
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	85	85			

FILE NAME =	USER NAME = dintelmanjn	DESIGNED -	REVISED -
c:\pwork\pwidet\dintelmanjn\08287304	0876F47-shrplandgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 10/10/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	102-1R5-3,102-T5	WASHINGTON	46	3
			CONTRACT NO. 76F47	
ILLINOIS FED. AID PROJECT				

12-23-13