

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
				0005		0021					0005		0021
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 80% FED 20% STATE	PARK, LANES 80% FED 10% CITY 10% STATE	TRAFFIC SIG. 80% FED 13.3% STATE 6.7% CITY	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 80% FED 20% STATE	PARK, LANES 80% FED 10% CITY 10% STATE	TRAFFIC SIG. 80% FED 13.3% STATE 6.7% CITY
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	575	575			70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	175	175			70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	37.5	37.5			70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1			70300100	SHORT TERM PAVEMENT MARKING	FOOT	3997	3997		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	9	9			70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1012	1012		
63200310	GUARDRAIL REMOVAL	FOOT	475	475			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	63182	63182		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9			70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	532	532		
67100100	MOBILIZATION	L SUM	1	1			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2137	2137		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	248	248		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1332	1332		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			* 72000100	SIGN PANEL - TYPE 1	SQ FT	5			5
							* 72000200	SIGN PANEL - TYPE 2	SQ FT	20			20

*** SPECIALTY ITEMS**

FILE NAME :	USER NAME : dintelman.jn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pe\work\pudat\dintelman\j\0207304	027GF47.she-plan.dgn	DRAWN -	REVISED -			42	102-IRS-3,102-TS	WASHINGTON	46	4	
	PLOT SCALE : 100.0000 ' / in.	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 76F47			
	PLOT DATE : 10/10/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					