

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION	EDGE LINE (LT) SOLID WHITE 4"	NPZ - SB SOLID YELLOW 4"	SKIP-DASH 10'-30' YELLOW 4"	NPZ - NB SOLID YELLOW 4"	EDGE LINE (RT) SOLID WHITE 4"	LANE LINE SOLID WHITE 4"	PAINTED MEDIAN SOLID YELLOW 4"	DIAGONALS SOLID YELLOW 12"	REMARKS
STATION TO STATION	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	
0+06 - 0+20	14				14				
0+20 - 4+33	413	413		413	413				DOUBLE YELLOW
4+33 - 5+02		69		69	69				DOUBLE YELLOW, WEST 26TH ST
5+02 - 6+10	108	108		108	108				DOUBLE YELLOW
6+10 - 7+40		130		130	130				DOUBLE YELLOW, LOGAN AVE
7+40 - 7+84	44	44		44	44				DOUBLE YELLOW
7+84 - 13+14	530	530	133		530				
13+14 - 19+13	599		150		599				
19+13 - 23+05	392		98	392	392				
23+05 - 31+00	795	795		795	795				DOUBLE YELLOW
31+00 - 35+42	442	442	111		442				
35+42 - 37+67	225		56		225				
37+67 - 42+00	433		108	433	433				
42+00 - 44+90	290	290		290	290				DOUBLE YELLOW
44+90 - 50+09	519	519	130		519				
50+09 - 64+13	1404		351		1404				
64+13 - 65+35			31		122				KONZEN CT
65+35 - 65+72	37		9		37				
65+72 - 71+43	571		143	571	571				
71+43 - 79+00	757	757		757	757				DOUBLE YELLOW
79+00 - 85+00						97	2290	260	SEE DETAIL
85+00 - 85+62									PONTOON RD OMISSION
85+62 - 92+08						99	2480	305	SEE DETAIL
92+08 - 95+12	304	304		304	304				DOUBLE YELLOW
95+12 - 96+55	143	143		143	143				SEE DETAIL
SUBTOTAL	8020	4544	1320	4449	8341	196	4770	565	
TOTAL				31640				565	

PATCHING SCHEDULE

LOCATION	LENGTH	WIDTH	CLASS D PATCHES TYPE II, 13"	
STATION	LT / RT	(FEET)	(FEET)	
45+07	RT	18	4	8.00
45+66	RT	21	4	9.33
46+16	RT	33	4	14.67
66+10	RT	26	4	11.56
66+75	RT	26	5	14.44
SUBTOTAL				58
15% ANTICIPATED FAILURES				9
TOTAL				67

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER TWO WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER ONE WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER ONE WAY CRYSTAL	REMARKS
STATION TO STATION	(EACH)	(EACH)	(EACH)	(EACH)	
0+20 - 79+00	99	99			
79+00 - 85+00	48		31	3	SEE DETAIL
85+00 - 85+62					PONTOON RD OMISSION
85+62 - 92+08	49		33	3	SEE DETAIL
92+08 - 95+12	4	4			
95+12 - 96+55	2		2		SEE DETAIL
SUBTOTAL	202	103	66	6	
TOTAL	202		175		

THERMOPLASTIC PAVEMENT MARKING SCHEDULE (CONT.)

LOCATION	CROSSWALK SOLID WHITE 12"	STOP BARS SOLID WHITE 24"	LETTERS & SYMBOLS WHITE	REMARKS
STATION	LT / RT	(FOOT)	(FOOT)	(SQ FT)
0+03	LT & RT	104		
0+20	LT		25	
39+89	RT		11	
40+14	RT			61.2 RAILROAD "X" AND "R"s
40+39	RT		11	
43+39	RT		11	
44+33	LT		11	
47+33	LT		11	
47+58	LT			61.2 RAILROAD "X" AND "R"s
47+83	LT		11	
68+59	RT		11	
68+84	RT			61.2 RAILROAD "X" AND "R"s
69+09	RT		11	
72+09	RT		11	
73+29	LT		11	
76+29	LT		11	
76+54	LT			61.2 RAILROAD "X" AND "R"s
76+79	LT		11	
83+99	TURN LANE			15.6 LEFT TURN ARROW
84+46	TURN LANE			15.6 LEFT TURN ARROW
84+71	TURN LANE & RT		39	
85+91	TURN LANE & LT		33	
86+16	TURN LANE			15.6 LEFT TURN ARROW
86+65	TURN LANE			15.6 LEFT TURN ARROW
TOTAL		104	229	307.2

SHOULDER SCHEDULE - RIGHT

LOCATION	EARTH EXCAVATION	FILTER FABRIC	POROUS GRANULAR EMBANKMENT, SPECIAL	AGGREGATE WEDGE SHOULDERS, TYPE B	BITUMINOUS SURFACE TREATMENT (CLASS A-2)				REMARKS
					BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	
STATION TO STATION	WIDTH (FT)	(CU YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)
0+00 - 17+41	8			181	2.42	4.52	15.5	15.5	
17+41 - 17+81									C.E. (TOTAL GATE 9)
17+81 - 20+85	8	75	270	67	32	0.42	0.79	2.7	2.7
20+85 - 21+15									C.E. (TOTAL GATE 8)
21+15 - 21+88	8	18	65	16	8	0.10	0.19	0.6	0.6
21+88 - 22+28									C.E. (TOTAL GATE 7)
22+28 - 23+45	8	29	104	26	12	0.16	0.30	1.0	1.0
23+45 - 24+55									C.E. (TOTAL GATE 5/6)
24+55 - 25+63	8	27	96	24	11	0.15	0.28	1.0	1.0
25+63 - 26+23									C.E. (TOTAL GATE 4)
26+23 - 33+19	8			72	0.97	1.81	6.2	6.2	
33+19 - 35+29	8	52	187	47	22	0.29	0.55	1.9	1.9
35+29 - 43+61	8			86	1.16	2.16	7.4	7.4	
43+61 - 44+11									RAILROAD
44+11 - 55+43	8			117	1.57	2.94	10.1	10.1	
55+43 - 56+69									C.E. (INS RAILROAD)
56+69 - 61+03	8			45	0.60	1.13	3.9	3.9	
61+03 - 72+51	5			74	1.00	1.86	6.4	6.4	
72+51 - 72+87									RAILROAD
72+87 - 85+00	5			79	1.05	1.97	6.7	6.7	
TOTAL		201	722	180	739	9.9	18.5	63	63