

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 100% STATE		
20200100	EARTH EXCAVATION	CU YD	338	338		
28200200	FILTER FABRIC	SQ YD	1217	1217		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28.9	28.9		
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	34.3	34.3		
40300500	COVER COAT AGGREGATE	TON	117	117		
40300600	SEAL COAT AGGREGATE	TON	117	117		
40600300	AGGREGATE (PRIME COAT)	TON	51	51		
40600647	LEVELING BINDER (MACHINE METHOD), 1L-9.5FG, N90	TON	513	513		
40600990	TEMPORARY RAMP	SQ YD	372	372		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2324	2324		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	21564	21564		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	6103	6103		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	67	67		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1369	1369		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 100% STATE		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3279	3279		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	307.2	307.2		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31640	31640		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	669	669		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	229	229		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	364	364		

FILE NAME :	USER NAME : burnsideam	DESIGNED -	REVISED -
c:\pwwork\pwwork\burnsideam\10292675\10292675.dwg	9767-ehs-plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 10/21/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.J. RTE. 9094	SECTION (I-X)RS-4	COUNTY MADISON	TOTAL SHEETS 16	SHEET NO. 3
CONTRACT NO. 76F67				ILLINOIS FED. AID PROJECT