

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0021			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0021		
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0021 100% STATE		CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0021 100% STATE	
X0325076	WIDE AREA NETWORK	L SUM	1	1		X8950212	MODIFY EXISTING CONTROLLER CABINET, SPECIAL	EACH	2	2	
X0325077	FIBER OPTIC UTILITY MARKER	EACH	104	104		X0325086	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT, MULTI-DUCT	FOOT	60	60	
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	1	1		X8102839	UNDERGROUND CONDUIT, PVC, 4" DIA., MULTI-DUCT	FOOT	32010	32010	
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	6	6		Ø 20076604	TRAINEES TRAINING PROGRAM GRADUATE	Hour	500	500	
X0325483	SFP-GE-L SFP MODULE	EACH	10	10		* 66900200	NON - SPECIAL WASTE DISPOSAL	CUYD	5	5	
X0325484	SFP-GE-Z SFP MODULE	EACH	4	4		* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	1	1		* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	
X0326912	3000 LAYER 2 SWITCH	EACH	5	5							
X0327096	ETHERNET MODEM	EACH	4	4							
X8110128	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC TYPE C	FOOT	130	130							
X8630103	CONTROLLER CABINET TYPE III, SPECIAL	EACH	1	1							
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	34210	34210							
X8780105	CONCRETE FOUNDATIONS (SPECIAL)	EACH	1	1							

* 66900200 NON - SPECIAL WASTE DISPOSAL CUYD 5 5

* 66900450 SPECIAL WASTE PLANS AND REPORTS L SUM 1 1

* 66900530 SOIL DISPOSAL ANALYSIS EACH 1 1



3 Ø 0042 * SPECIALTY ITEM ⚠ 1-8-14