

PAVEMENT RESURFACING SCHEDULE - MAINLINE

(SEE NOTE 1)

EASTBOUND LANES

LOCATION STATION TO STATION	LENGTH (INFO ONLY)	EXIST. PAVEMENT WIDTH	TEMP. RAMPS	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - 2 1/4"	POLY HMA SURFACE COURSE 1 1/2"	POLY HMA BINDER COURSE 2 1/4"	INCIDENTAL HMA SURFACING	PRIME COAT		NOTES		
									POLY. BIT. MAT' LS.	AGG.			
FAI 64 (I-64) EASTBOUND			FEET	FEET	SQ YD	SQ YD	SQ YD	TON	TON	TON	GAL	TON	
	5455+88.00	TO	5456+18.00	30.0	24.0	35.0	134		7		14	0.2	
Lt.	5471+00.00									17	18	0.3	Median Xover
	5456+18.00	TO	5493+65.00	3747.0	24.0		9992	844	1259		1808	30.1	
	5493+65.00	TO	5496+25.00	260.0	24.0		693	92			126	2.1	A+ Overpass
	5496+25.00	TO	5512+48.00	1623.0	24.0		4328	366	545		783	13.1	
SN 097-0038 - Sta. 5512+48 to Sta. 5519+36				688.0		27.0	268						2 Butt Joints
	5519+36.00	TO	5624+67.00	10531.0	24.0		28083	2371	3539		5081	84.7	
Lt.	5576+60.00									17	18	0.3	Median Xover
	5624+67.00	TO	5627+27.00	260.0	24.0		693	92			125	2.1	A+ Overpass
	5627+27.00	TO	5716+33.00	8906.0	24.0		23749	2005	2993		4297	71.6	
	5716+33.00	TO	5718+93.00	260.0	24.0		693	92			125	2.1	A+ Overpass
	5718+93.00	TO	5763+58.00	4465.0	24.0		11907	1005	1500		2154	35.9	
SN 097-0052 - Sta. 5763+58 to Sta. 5764+72				114.0		27.0	268						2 Butt Joints
	5764+72.00	TO	5800+02.00	3530.0	24.0		9414	795	1186		1703	28.4	
Lt.	5774+68.00									17	18	0.3	Median Xover
	5800+02.00	TO	5800+32.00	30.0	24.0	35.0	134		7		14	0.2	
EASTBOUND TOTALS					124	804	89,552	7676	11,022	51	16,286	271	

Note 1: For pay items related to structures, see sheets 27 to 51.

*(97-2-1)RS-1; BSMART 2012-1.2.3

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT RESURFACING SCHEDULE	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\pwsdot\mccordkr\d0282931\78282-sht-plan.dgn	DRAWN -	REVISED -	64				WHITE	54	10	
PLOT SCALE = 100.9772' / in.	CHECKED -	REVISED -	CONTRACT NO. 78282							
PLOT DATE = 10/29/2013	DATE -	REVISED -	SCALE:			SHEET	OF	SHEETS	STA.	TO