

**PAVEMENT RESURFACING SCHEDULE - MAINLINE**

(SEE NOTE 1)

**WESTBOUND LANES**

LOCATION STATION TO STATION	LENGTH (INFO ONLY)	EXIST. PAVEMENT WIDTH	TEMP. RAMPS	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - 2 1/4"	POLY HMA SURFACE COURSE 1 1/2"	POLY HMA BINDER COURSE 2 1/4"	INCIDENTAL HMA SURFACING	PRIME COAT		NOTES		
									POLY. BIT. MAT' LS.	AGG.			
FAI 64 ( I-64) WESTBOUND			FEET	FEET	SQ YD	SQ YD	SQ YD	TON	TON	TON	GAL	TON	
5455+88.00 TO 5456+18.00	30.0	24.0	35.0	134				7			14	0.2	
5456+18.00 TO 5493+65.00	3747.0	24.0			9992			844	1259		1808	30.1	
5493+65.00 TO 5496+25.00	260.0	24.0			693			92			126	2.1	At Overpass
5496+25.00 TO 5512+48.00	1623.0	24.0			4328			366	545		783	13.1	
SN 097-0039 - Sta. 5512+48 to Sta. 5519+36			688.0		27.0	268							
5519+36.00 TO 5624+67.00	10531.0	24.0			28083			2371	3539		5081	84.7	
Lt. 5579+65.00 TO 5587+48.40	783.4									37	78	1.3	See Note 2
Lt. 5617+58.00 TO 5623+44.54	586.5									28	59	1.0	See Note 2
5624+67.00 TO 5627+27.00	260.0	24.0			693			92			125	2.1	At Overpass
5627+27.00 TO 5716+33.00	8906.0	24.0			23749			2005	2993		4297	71.6	
5716+33.00 TO 5718+93.00	260.0	24.0			693			92			125	2.1	At Overpass
5718+93.00 TO 5763+58.00	4465.0	24.0			11907			1005	1500		2154	35.9	
SN 097-0051 - Sta. 5763+58 to Sta. 5764+72			114.0		27.0	268							
5764+72.00 TO 5800+02.00	3530.0	24.0			9414			795	1186		1703	28.4	
5800+02.00 TO 5800+32.00	30.0	24.0	35.0	134				7			14	0.2	
<b>WESTBOUND TOTALS</b>					<b>124</b>	<b>804</b>	<b>89,552</b>	<b>7676</b>	<b>11,022</b>	<b>65</b>	<b>16,369</b>	<b>272.9</b>	

Note 1: For pay items related to structures, see sheets 27 to 51.

Note 2: Existing Weigh Station entrance and exit ramps at these locations.

**SUMMARY OF PAVEMENT CALCULATIONS FOR FAI 64 MAINLINE AND RAMPS**

	TEMP. RAMPS	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - 2 1/4"	POLY HMA SURFACE COURSE	POLY HMA BINDER COURSE	INCIDENTAL HMA SURFACING	PRIME COAT	
							POLY. BIT. MAT' LS.	AGG.
	SQ YD	SQ YD	SQ YD	TON	TON	TON	GAL	TON
FAI 64 EASTBOUND LANES	124	804	89552	7676	11022	51	16286	271.4
FAI 64 WESTBOUND LANES	124	804	89552	7676	11022	65	16369	272.9
<b>PROJECT TOTALS</b>	<b>248</b>	<b>1608</b>	<b>179,104</b>	<b>15,352</b>	<b>22,044</b>	<b>116</b>	<b>32,655</b>	<b>544.3</b>

\*(97-2-1)RS-1; BSMART 2012-1,2,3

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT RESURFACING SCHEDULE CONTINUED</b>				F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\pwsdot\mccordkr\d0282931\78282-sht-plan.dgn	DRAWN -	REVISED -	64							WHITE	54	11	
PLOT SCALE = 100.9772' / in.	CHECKED -	REVISED -	SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 78282						
PLOT DATE = 10/29/2013	DATE -	REVISED -					ILLINOIS FED. AID PROJECT						