

**PAVEMENT MARKING SCHEDULE  
EASTBOUND PAVEMENT MARKING**

LOCATION STATION TO STATION	LENGTH (INFORMATION ONLY)	PREFORMED PLASTIC LINE 4"		PREFORMED PLASTIC LINE 6"	TEMP PAVT MRK - LINE 4"		TEMP PAVT MRK - LINE 6"	SHORT-TERM PAVT MRK - LINE 4"		SHORT-TERM PVT MRK - LINE 6"	NOTES
		SOLID YELLOW	SOLID WHITE		SOLID YELLOW	SOLID WHITE		SOLID YELLOW	SOLID WHITE		
		LT. EDGE OF PAVT.	RT. EDGE OF PAVT.	WHITE (SKIP-DASH)	LT. EDGE OF PAVT.	RT. EDGE OF PAVT.	MAINLINE SKIP-DASH	LT. SHLD. DIAG. STRIPE	RT. SHLD. DIAG. STRIPE	MAINLINE SKIP-DASH	
FAI 64 (I-64) EASTBOUND	FEET	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
MAINLINE											
5455+88.00 TO 5512+48.00	5660	5660	5660	1415	5660	5660	1415	906	906	2264	
STR. NO. 097-0038	688	688	688	172	688	688	172	110	110	275	
5519+36.00 TO 5763+58.00	24422	24422	24422	6106	24422	24422	6106	3908	3908	9769	
STR. NO. 097-0052	114	114	114	29	114	114	29	19	19	46	
5764+72.00 TO 5800+32.00	3560	3560	3560	890	3560	3560	890	570	570	1424	
STR. NO. 097-0001	295	295	295	74	295	295	74	48	48	120	
SUBTOTALS		34739	34739	8686	34739	34739	8686	5561	5561	13898	
EASTBOUND TOTALS		69478		8686	69478		8686	25020			

**WESTBOUND PAVEMENT MARKING**

LOCATION STATION TO STATION	LENGTH (INFORMATION ONLY)	PREFORMED PLASTIC LINE 4"		PREFORMED PLASTIC LINE 6"	TEMP PAVT MRK - LINE 4"		TEMP PAVT MRK - LINE 6"	SHORT-TERM PAVT MRK - LINE 4"		SHORT-TERM PVT MRK - LINE 6"	NOTES
		SOLID WHITE	SOLID YELLOW		SOLID WHITE	SOLID YELLOW		SOLID WHITE	SOLID YELLOW		
		LT. EDGE OF PAVT.	RT. EDGE OF PAVT.	WHITE (SKIP-DASH)	LT. EDGE OF PAVT.	RT. EDGE OF PAVT.	MAINLINE SKIP-DASH	LT. SHLD. DIAG. STRIPE	RT. SHLD. DIAG. STRIPE	MAINLINE SKIP-DASH	
FAI 64 (I-64) WESTBOUND	FEET	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FEET	
MAINLINE											
5455+88.00 TO 5512+48.00	5660	5660	5660	1415	5660	5660	1415	906	906	2264	
STR. NO. 097-0039	688	688	688	172	688	688	172	110	110	275	
LT 5519+36.00 TO 5573+65.00	5429	5429			5429			869			On Left Shld.
LT 5587+48.00 TO 5617+58.00	3010	3010			3010			482			On Left Shld.
LT 5622+88.00 TO 5763+58.00	14070	14070			14070			2251			On Left Shld.
RT 5519+36.00 TO 5763+58.00	24422		24422	6106		24422	6106		3908	9769	On Right Shld.
STR. NO. 097-0051	114	114	114	29	114	114	29	19	19	46	
5764+72.00 TO 5800+32.00	3560	3560	3560	890	3560	3560	890	570	570	1424	
STR. NO. 097-0052	295	295	295	74	295	295	74	48	48	120	
SUBTOTALS		32826	34739	8686	32826	34739	8686	5255	5561	13898	
WESTBOUND TOTALS		67565		8686	67565		8686	24714			
PROJECT TOTALS		137,043		17,372	134,043		17,372	49,734			