

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	Existing Length (Inform. Only)	GUARDRAIL REMOVAL	SPBGR TYPE A. 6 FT. POSTS	TRAFFIC BARRIER TERMINAL		TERMINAL MARKERS - DA	GUARDRAIL MARKERS TY. A
				TY 1, SPL (TAN)	TYPE 6		
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
EASTBOUND FAI 64							
097-0038 WEST OUTSIDE APPROACH							
RT 5509+54.25				1		1	
RT 5510+28.00 TO RT 5512+48.00	220	220					
RT 5510+04.25 TO RT 5511+91.75			187.5				4
RT 5512+48.00					1		
097-0038 WEST MEDIAN APPROACH							
LT 5509+04.25				1		1	
LT 5510+93.00 TO LT 5512+48.00	158	158					
LT 5509+54.25 TO LT 5511+91.75			237.5				4
LT 5512+48.00					1		
097-0052 WEST OUTSIDE APPROACH							
RT 5760+64.25				1		1	
RT 5761+12.00 TO RT 5763+58.00	246	246					
RT 5761+14.25 TO RT 5763+01.75			187.5				4
RT 5763+58.00					1		
097-0052 WEST MEDIAN APPROACH							
LT 5760+14.25				1		1	
LT 5762+00.00 TO LT 5763+58.00	162	162					
LT 5760+64.25 TO LT 5763+01.72			237.5				4
LT 5763+58.00					1		
SUBTOTALS FAI 64 EASTBOUND		786	850	4	4	4	16
WESTBOUND FAI 64							
097-0039 EAST OUTSIDE APPROACH							
LT 5519+36.00					1		
LT 5519+36.00 TO LT 5521+56.00	220	220					
LT 5519+92.25 TO LT 5521+79.75			187.5				4
LT 5522+29.75				1		1	
097-0039 EAST MEDIAN APPROACH							
RT 5519+36.00					1		
RT 5519+36.00 TO RT 5520+90.00	157	157					
RT 5519+92.25 TO RT 5522+29.75			237.5				4
RT 5522+29.75				1		1	
097-0051 EAST OUTSIDE APPROACH							
LT 5764+72.00					1		
LT 5764+72.00 TO LT 5766+92.00	220	220					
LT 5765+28.25 TO LT 5767+15.75			187.5				4
LT 5767+65.75				1		1	
097-0051 EAST MEDIAN APPROACH							
RT 5764+72.00					1		
RT 5764+72.00 TO RT 5766+26.00	156	156					
RT 5765+28.25 TO RT 5767+65.75			237.5				4
RT 5768+15.75				1		1	
SUBTOTALS FAI 64 WESTBOUND		753	850	4	4	4	16
PROJECT TOTALS:	1539.00	1539	1700	8	8	8	32