







## DRAIN EXTENSION DETAIL 94 Locations on SN 097-0038

94 Locations on SN 097-0039

## Notes:

Plug every other existing deck drain and all that are within ±10' of the existing substructure. Locations shall be subject to approval by the Engineer. Post shall be normal to parapet.

1'-9''

\*In lieu of the cast-in-place anchor device shown, the Contractor has the option of drilling and setting stainless steel anchor rods of the same diameter and arade as the specified cap screws according to Article 509.06 of the Standard Specifications. Embedment shall be according to the manufacturer's specifications.

Removal and and re-erection of the existing aluminum handrail, rail post, and all new applicable hardware, including labor and installation shall be included in the cost of Concrete Removal.

Concrete removal. Removal of the existing drain extensions will be included in the cost of Floor Drain Extensions. (No Salvage) \*\*Verify that this dimension will work in the field before ordering the material or use  $4^{5}_{8}$ '' if available. \*\*\* Verify that there is enough existing drain extending out of the concrete to weld extension. Otherwise use a flange extension drilled into the concrete cubicat to concrete

extension drilled into the concrete, subject to approval by the Engineer.

				<u>STREETORE NO. 037 0035 (N.</u>						<u> </u>
									*(97-2-1)RS-1	.; BSMART 2012-1,2,3
FILE NAME =	USER NAME = halsteadtw	DESIGNED - TWH	REVISED -			DRAINS, RAILING, ETC. DE		F.A.I RTF	SECTION	COUNTY TOTAL SHEET
c:\pw_work\pwidot\halsteadtw\d0344460\	stt-pln.dgn	DRAWN - TWH	REVISED -	STATE OF ILLINOIS		SN 097–0038 (EB) & 097–0039 (WB)		64	•	WHITE 54 37
	PLOT SCALE = 3.0000 ' / in.	CHECKED - MAS	REVISED -	DEPARTMENT OF TRANSPORTATION	311 U37-0036 (EB) & U37-0039 (WVD)				CONTRACT NO.78282	
	PLOT DATE = 10/7/2013	DATE - 10/15/09	REVISED -		SCALE: SHEET NO. 11 OF 25 SHEETS STA. TO STA.			FED. ROAD (	ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

## BILL OF MATERIAL

Item	Unit	Total
Floor Drain Extension	Each	188
Plug Existing Deck Drains	Each	184
Structural Repair of Concrete (Depth ≤ Inches)	Sq. Ft.	66
(Depth ≤ Inches)	59. 77.	

DRAINS, RAILING & CONCRETE REPAIR DETAILS WHITE COUNTY STRUCTURE NO. 097-0038 (E.B.) STRUCTURE NO. 097-0039 (W.B)