

SOIL REPORT AVAILABILITY

All soils data collected and processed for the Soils Report made in conjunction with the design of this improvement is on file at the District Office where it is available for the inspection of Contractors or prospective bidders. By submitting a bid, the Contractor acknowledges that the Soils Report has been made available and is aware of the report contents and appendices.

AVAILABILITY OF ELECTRONIC FILES

Micro Station and GEOPAK files of this project will be made available to the Contractor. If there is a conflict between the electronic files and the printed contract plans and documents, the printed contract plans and documents shall take precedence over the electronic files. The Contractor shall accept all risk associated with using the electronic files and shall hold the Department harmless for any errors or omissions in the electronic files and the data contained therein. Errors or delays resulting from the use of the electronic files by the Contractor shall not result in an extension of time for any interim or final completion date or shall not be considered cause for additional compensation. The Contractor shall not use, share, or distribute these electronic files except for the purpose of constructing this contract. Any claims by third parties due to use or errors shall be the responsibility of the Contractor. The Contractor shall include this disclaimer with the transfer of these electronic files to any other parties and shall include appropriate language binding them to similar responsibilities.

UTILITIES - LOCATIONS / INFORMATION ON PLANS

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown — all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

PLAN ELEVATIONS - U. S. G. S. MEAN SEA LEVEL DATUM

All elevations shown on the plans are established from U. S. G. S. mean sea level datum.

PROPERTY OWNER ACCESS REQUIREMENTS

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangements are made in writing by the Contractor with the property owners with a copy to the Engineer for short-term closures.

CONSECUTIVE SIDE STREET (ROAD) CLOSURE - PROHIBITED

1. No two consecutive side streets (roads) may be closed at the same time during construction. The Contractor must alternate streets (roads).
2. Adjacent side roads will not be closed simultaneously. BLR Standard 21 shall be used for all local road closures without any entrances within the closed area. BLR Standard 22 can be used where it is necessary to allow local traffic access.

TREE REMOVAL

The District Four Tree Committee should be contacted and prior approval obtained for any tree removal beyond the limits/locations included in the plans.

TEMPORARY MATERIAL REQUIREMENTS - UTILITY AND DRIVEWAY CROSSINGS

Incidental hot-mix asphalt surface shall be used for all temporary side road crossings. Aggregate surface course may be used for all driveway crossings except during winter shutdown in accordance with Article 107.09.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Cultural and Natural Resources Review of Borrow Areas)
- * BDE Form 2290 (Waste/Use Area Review)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form-D4 PI0100
- * Color photographs depicting the use area
- * Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances and six weeks for the required borrow site environmental clearances.

BUTT JOINT CUTTING TIME RESTRICTION

Butt joints shall not be milled more than three (3) days prior to placement of the HMA surface course.

PAVING SURFACE COURSE

Continuous paving operations on the main roadway shall be maintained at all times during the construction of the hot-mix asphalt surface. No interruptions for side roads, entrances, turn lanes, etc. will be allowed.

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

The Contractor shall consult with the Engineer in regard to the exact length of the box/pipe culverts, storm sewers, and/or pipe drains required prior to ordering these items.

ENGINEERS FIELD OFFICE

Add the following sentence to the end of paragraph 670.02 (i) and 670.04 (e):
All of the telephone lines provided shall have unpublished numbers.

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RTE 91 GENERAL NOTES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pedit\crespole\0330150\ND10	792-eh\ergonota.dgn	DRAWN -	REVISED -			1380	7W-1, R5-3	PEORIA	617	3	
Default	PLOT SCALE * 400.0000 / in.	CHECKED -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE * 8/15/2013	DATE -	REVISED -			CONTRACT NO. 88792 ILLINOIS FED. AID PROJECT					

1 12-27-13

JOB SPECIFIC NOTES

- Aggregate for temporary access shall be used during stage construction as directed by the Engineer. The Contractor will be responsible for maintaining of the access during stage construction. The removal of the aggregate will be included in the cost of the aggregate for temporary access pay item.
- CCC&G adjacent to existing pavement
The existing pavement edge shall be saw cut to provide a clean edge for CCC&G construction. This work shall be included in the unit cost of the CCC&G. Other methods of providing a clean edge may be used as approved by the Engineer.
- Existing drains
At locations where existing 3" or 4" clean water drains outleted into existing ditch it shall be cut or extended to drain into proposed ditch. Other locations might need to use the detail shown in the plans to connect to IDOT storm inlets.
- Excavation required for PCC Base Course, Temporary widening, Bituminous Shoulders, Bituminous Base Course, and Aggregate Shoulders is measured and paid for as Earth Excavation.
- ① -Exploration Trench 52" Depth quantities has been provided for the purpose of locating unknown underground utilities and shall be used as directed by the engineer.

COMMITMENTS

- Parcel No. 4ACC017 - Mr. & Mrs. Sutton
Mailing address: 102 South Fourth Street, Dunlap, IL. 61525
the contractor shall take care not to damage any portion of MR. Sutton's fence at 102 South Fourth st. This includes the portion of the fence that are inside the temporary easement. Any such damage shall be the responsibility of the contractor.
- Parcel No. 4ACC002 - Mr. Jeffrey Brandstatter
Mailing address: 13707 North Route 91, Dunlap, IL. 61525
the drive thru for Better Banks ATM, Sta. 100+75 to 101+45, will remain open throughout construction.
- Parcel No. 4ACC009 - Mr. & Mrs. Pittenger
Mailing address: 4022 West Legion Hall Road, Dunlap, IL. 61525
the Resident Engineer will contact the property owner at least 30 days prior to working on the entrance at Sta. 110+46.38 and Sta. 110+81.08. contact Dale or Diane Pittenger at (309) 243-1879 Home or (309)208-0906 Cell
- Parcel No. 4ACC072 - Dorothy M. Harlan Trust
Mailing address: 6926 N. Stallworth, Apt. 317, Peoria, IL. 61525
The state of Illinois, Department of Transportation agrees to the following regarding the above mentioned parcel.
 - Any field tile that are intercepted or disturbed will be reconnected or repaired by the Department of Transportation's contractor.
 - The crops planted for the 2013 season may be harvested by your tenant.
- Parcel No. 4ACC010 & TE - Harold D. Turley Revocable Living Trust
Mailing address: 2406 North Maryland, Peoria, IL. 61603
-The department's contractor will layout and restripe the parking lot after the use of the temporary easement area is complete. S & S Property Management shall be contacted at (309)691-1919 to coordinate parking issues.
 - The mailboxes are to be relocated in the same location when construction is complete. The barrier poles that protect the mailboxes will be worked around and not disturbed during construction operation.
- Parcel No. 4ACC064 & TE - Brett Crossman
Mailing address: 400 South Breckenridge Dr. Dunlap, IL. 61525
- The fence and pear tree located within the temporary easement area will not be disturbed during construction and will be able to remain in place in their current location.
- Parcel No. 4ACC034 - Dunlap Community Unit School District No. 323
Lisa Barker, Assistant Superintendent
Mailing address: 5220 West Legion Hall Road, Box 395 Dunlap, IL. 61525
-The contractor shall pay attention to not disturb existing Fiber Optic along Legion Hall Road during the removal and replacement of pipe culverts and the High School entrance at approximate station 17+25. The contractor shall notify the school district at least two weeks prior to beginning construction at the above referenced location. The contractor shall be responsible for the relocation and/or replacement of any existing fiber optic cable damaged within the proposed construction limits in the above referenced area.

① 12-27-13

FILE NAME *	USER NAME * crospele	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RTE 91 GENERAL NOTES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\purdot\crospele\0330150\040	792-ent-gensite.dgn	DRAWN -	REVISED -			1380	7W-1, RS-3	PEORIA	617	5	
Default	PLOT SCALE * 400,0000' / 1"	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
	PLOT DATE * 8/13/2013	DATE -	REVISED -								