

MODEL: 44001.DWG  
 FILE NAME: p:\up\lanscom.dat\illinois.gov\PWIDOT\Documents\DOT\_Offices\District 5\Projects\DS70892\CAD\Drawings\Structures\DS70892-shi-SDO.dgn

<b>CHAMPAIGN COUNTY STRUCTURE IMPROVEMENT F.A.I. 74 S.N. 010-0031 (EB) STA. 857+84.98 S.N. 010-0032 (WB) STA. 858+08.72 90% FED 10% STATE</b>	<b>CHAMPAIGN COUNTY STRUCTURE IMPROVEMENT F.A.I. 74 S.N. 010-0089 STA. 762+00.00 90% FED 10% STATE</b>	<b>CHAMPAIGN COUNTY STRUCTURE IMPROVEMENT F.A.I. 74 S.N. 010-0175 STA. 430+00.00 90% FED 10% STATE</b>
---	--	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CHAMPAIGN COUNTY STRUCTURE IMPROVEMENT F.A.I. 74		
				0059 RURAL	0059 RURAL	0059 RURAL
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4.0	2.0	2.0	0.0
* 78008310	POLYUREA PAVEMENT MARKING, TYPE II- LINE 4"	FOOT	3,458.0	2,250.0	1,208.0	0.0
X0325748	ACRYLIC COATING	SQ YD	122.0	122.0	0.0	0.0
X0325749	FIBER WRAP	SQ FT	1,022.0	1,022.0	0.0	0.0
X0327640	REAL-TIME TRAFFIC CONTROL CENTRAL BASE UNIT	CAL MO	5.0	5.0	0.0	0.0
X0327641	REAL-TIME TRAFFIC CONTROL SENSOR UNIT	CAL MO	40.0	40.0	0.0	0.0
X1200030	FILLING INLETS, TEMPORARY	EACH	4.0	4.0	0.0	0.0
X2700001	TEMPORARY RUMBLE STRIPS (SPECIAL)	EACH	32.0	32.0	0.0	0.0
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	1,215.0	1,215.0	0.0	0.0
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	150.0	98.0	52.0	0.0
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0	0.5	0.5	0.0
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING, 5"	FOOT	3,458.0	2,250.0	1,208.0	0.0
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	51.0	51.0	0.0	0.0
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	919.0	0.0	919.0	0.0
Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	516.0	0.0	0.0	516.0

\* SPECIALTY ITEMS

USER NAME = shererjm	DESIGNED - JMS	REVISED -
DRAWN - JMS	CHECKED -	REVISED -
PLOT SCALE = 40.0000' / in.	DATE - 021119	REVISED -
PLOT DATE = 10/16/2019		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6.7)BDR	CHAMPAIGN	99	6
CONTRACT NO. 70892			ILLINOIS FED. AID PROJECT	



