

0-02174-6027  
 SN 065-0002  
 100% STATE  
 SN 065-0002  
 0047-RURAL  
 MENARD

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
50157300	PROTECTIVE SHIELD	SO YD	236	236
50102400	CONCRETE REMOVAL	CU YD	79	79
50300255	CONCRETE SUPERSTRUCTURE	CU YD	79	79
50300300	PROTECTIVE COAT	SO YD	367	367
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8430	8430
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	900	900
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2



△ REV. 1-7-2020

MODEL: D:\pilot  
 FILE NAME: C:\control\OPERATIONS\Bridges\BridgesPlans CAD\72L48 - 0650002.parapetplan sheet.dgn

USER NAME = dudleybm	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/10/2019	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
34	(2) BRR	MENARD	10	3
			CONTRACT NO. 72L48	
ILLINOIS FED. AID PROJECT				