

80% FED
20% STATE

80% FED
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005	-----
40400001	FIBER-MODIFIED ASPHALT CRACK SEALING	FOOT	51781	51781	
40400020	BUMP REMOVAL	EACH	46	46	
40500061	CAPE SEAL, TYPE II	SQ YD	86155	86155	
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	318	318	
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	18	18	
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	36	36	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1	
	701306				
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15000	15000	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	990	990	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	72761	72761	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	72761	72761	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	375	375	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005	-----
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	375	375	
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	23759	23759	
X0327979	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	23759	23759	



* *
 MODEL: Default
 FILE NAME: P:\p1\p1room.dwg
 ILLINOIS.GCP:PWIDOT\Documents\DOT_Offices\District_7\Projects\74951\CADD\DATA\CAD\Sheet\74951-shs-S00.dgn

* SPECIALTY ITEM

△ REV. 1-7-2020

REV. - MS

USER NAME = steffenmk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/18/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
776	(101) PVMT PRSV	WAYNE	6	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74951	

1
PAVEMENT MARKING REMOVAL - GRINDING

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH FOOT	PAVEMENT MARKING REMOVAL - WATER BLASTING SQ FT	PAINT PAVEMENT MARKING - LINE 4" WHITE FOOT	PAINT PAVEMENT MARKING - LINE 4" YELLOW FOOT	SHORT-TERM PAVEMENT MARKING FOOT	TEMPORARY PAVEMENT MARKING - LINE 4" FOOT	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKERS EACH
14+80.00 TO 142+05.50	12725.5	9382.7	25351	3181	6360	28532	159	159
142+05.50 TO 143+94.50	189.0	140	378	47	100	425	2	2
143+94.50 TO 180+50.70	3656.2	2556	7072	914	1820	7987	46	46
180+50.70 = 181+08.90	STATION EQUATION							
181+08.90 TO 315+50.00	13441.1	11680	26458	9359	6720	35817	168	168
PROJECT TOTAL		23759	59260	13502	15000	72761	375	375

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	WIDTH FOOT	CAPE SEAL, TYPE II SQ YD
14+80.00 TO 29+53.00	1,473.0	26.0	4,255.3
29+53.00 TO 29+83.00	30.0	26.0	86.7
29+83.00 TO 30+83.00	100.0	26.0	288.9
30+83.00 TO 31+13.00	30.0	26.0	86.7
31+13.00 TO 65+10.00	3,397.0	26.0	9,813.6
65+10.00 TO 65+40.00	30.0	26.0	86.7
65+40.00 TO 69+76.00	436.0	26.0	1,259.6
69+76.00 TO 70+06.00	30.0	26.0	86.7
70+06.00 TO 141+75.50	7,169.5	26.0	20,711.9
141+75.50 TO 142+05.50	30.0	26.0	86.7
142+05.50 TO 143+94.50	189.0		
143+94.50 TO 144+24.50	30.0	26.0	86.7
144+24.50 TO 158+30.00	1,405.5	26.0	4,060.3
158+30.00 TO 158+60.00	30.0	26.0	86.7
158+60.00 TO 159+60.00	100.0	26.0	288.9
159+60.00 TO 159+90.00	30.0	26.0	86.7
159+90.00 TO 180+50.70	2,060.7	26.0	5,953.1
180+50.70 = 181+08.90			
181+08.90 TO 203+72.50	2,263.6	26.0	6,539.3
203+72.50 TO 204+02.50	30.0	26.0	86.7
204+02.50 TO 204+52.50	50.0	26.0	144.4
204+52.50 TO 204+83.50	31.0	26.0	89.6
204+83.50 TO 205+33.50	50.0	26.0	144.4
205+33.50 TO 205+63.50	30.0	26.0	86.7
205+63.50 TO 210+61.00	497.5	26.0	1,437.2
210+61.00 TO 210+91.00	30.0	26.0	86.7
210+91.00 TO 211+91.00	100.0	26.0	288.9
211+91.00 TO 212+21.00	30.0	26.0	86.7
212+21.00 TO 256+41.00	4,420.0	26.0	12,768.9
256+41.00 TO 256+71.00	30.0	26.0	86.7
256+71.00 TO 257+71.00	100.0	26.0	288.9
257+71.00 TO 258+01.00	30.0	26.0	86.7
258+01.00 TO 284+86.00	2,685.0	26.0	7,756.7
284+86.00 TO 285+16.00	30.0	26.0	86.7
285+16.00 TO 286+16.00	100.0	26.0	288.9
286+16.00 TO 286+46.00	30.0	26.0	86.7
286+46.00 TO 315+50.00	2,904.0	26.0	8,389.3
PROJECT TOTALS	30,012		86,155

MODEL: Default
FILE NAME: p:\highway\com.dpt.illinois.gov\PIVDOT\Documents\DOT_Offices\District 7\Projects\74951\CADD\Drawings\CAD\Drawings\74951-rhs-schedule.dgn

1 REV. 1-7-2020

USER NAME = steffemk	DESIGNED -	REVISED -
DRAWN -	REVISOR -	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 11/12/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES AND DETAIL SHEET			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
776	(101) PVMT PRSV	WAYNE	6	5
CONTRACT NO. 74951				
ILLINOIS FED. AID PROJECT				