



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2020

SUBJECT: FAP Route 586A (IL 162)  
Project NHPP-5KMJ (278)  
Section (51,59,31)RS-4  
Madison County  
Contract No. 76K43  
Item No. 61, January 17, 2020 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices in iCX
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 87 to the Special Provisions
4. Revised sheet 7 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

PROGRESS PAYMENTS (BDE).....55  
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE).....56  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....65  
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE) .....75  
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....76  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....76  
TEMPORARY PAVEMENT MARKING (BDE).....77  
TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (BDE).....79  
TRAFFIC CONTROL DEVICES - CONES (BDE).....80  
TRAINING SPECIAL PROVISIONS (BDE) .....80  
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION...83  
WARM MIX ASPHALT (BDE) .....85  
WEEKLY DBE TRUCKING REPORTS (BDE).....86  
WORKING DAYS (BDE).....86  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....87

## **REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES**

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Work Areas.** The excavated soil and groundwater within the work areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

The following areas should be monitored by the Environmental Firm for soil contamination and workers protection.

### **Site 3440-1 – Circle K Gas Station, 6559 IL 162, Maryville, Madison County**

- All excavation in the northwest quadrant of Illinois 162 and North Center Street: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3440-2 – Commercial Building, 6558 IL 162, Maryville, Madison County**

- All excavation in the southwest quadrant of Illinois 162 and North Center Street: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **Site 3440-1 (Circle K Gas Station) and 3440-2 (Commercial Building).**

Additional information on the above sites collected during the Phase I Engineering process is available through the District’s Environmental Studies Unit (DESU).