



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 6, 2020

SUBJECT: Route FAS Route 1254 (CH 16)
Section 13-00025-00-BR
Putnam County
Contract No. 89708
Item 118
January 17, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 6 of the special provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Removal of the existing right-of-way markers will be paid for at the contract unit price per Each for REMOVE RIGHT-OF-WAY MARKERS.

SAND DRAINAGE BLANKET

This work shall include constructing a sand drainage blanket as shown in the plans.

Sand shall meet the requirements of Article 1003.04, except gradation FA 6 is not allowed.

The existing ground surface shall be leveled as shown on the plans or as directed by the Engineer prior to placing sand. Ground preparation and sand placement shall be to according to Section 205. Sand shall be compacted to a minimum of 90 percent of the standard laboratory density.

Sand Drainage Blanket will be measured and paid at the contract unit price per cubic yard for SAND DRAINAGE BLANKET.

ARTICULATED BLOCK REVETMENT MAT

The Articulated Block Revetment Mat shall be an open cell class and be capable of resisting a velocity of 10.25 fps at a flow rate of 1520cfs, except the Articulated Block Revetment Mat shall be a closed cell class downstream of the gabion drop structure for a distance of 10 feet.

Shop drawings shall be submitted according to Article 1042.03(b) to the Design Engineer for approval. Shop drawings will include block size, block weight (mass), mat details, toe in details and anchoring details. Any changes needed to the design or any additional cost incurred shall be the responsibility of the Contractor.

PERMIT

This project is covered under Regional Permit 38 as contained herein provided all terms and conditions are met.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Site 3146-1: Commercial Building, 14080 W. Bottom Road, unincorporated Granville Township, Putnam County, Illinois

) Station 84+75 to Station 85+30, 0 to 30 ft LT. The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.