

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE ROADWAY	
				0005	URBAN
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	37	37	
44201299	DOWEL BARS 1 1/2"	EACH	42	42	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	5	5	
44213200	SAW CUTS	FOOT	84	84	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	30	30	
50105220	PIPE CULVERT REMOVAL	FOOT	76	76	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	92	92	
54261718	STEEL FLARED END SECTIONS 18"	EACH	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	56	56	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1500	1500	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	251	251	
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	655	655	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE ROADWAY	
				0005	URBAN
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	3	3	
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	3	3	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	655.2	655.2	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	18496	18496	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	214	214	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	214	214	
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	6167	6167	

* SPECIALTY ITEM

MODEL: Summary of Quantities 2 (Sheet)
FILE NAME: c:\pwworkspace\prmdf1018661\0876146-eh-SOO.dgn

⚠️ REVISED 1-7-2025

USER NAME = michael.berg	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 10/26/2024	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	133RS-7	MADISON	10	4
CONTRACT NO. 76L46				
ILLINOIS FED. AID PROJECT				