

SUMMARY OF QUANTITIES

COUNTY:	PERRY
ROUTE:	FAP 103
FUNDING:	80% FEDERAL 20% STATE
LOCATION:	RURAL
	ROADWAY
	0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	22,070	22,070
40600370	LONGITUDINAL JOINT SEALANT	FOOT	16,893	16,893
40600990	TEMPORARY RAMP	SQ YD	157	157
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	4,123	4,123
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	42
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	48,804	48,804
44201403	CLASS C PATCHES, TYPE II, 14 INCH	SQ YD	381	381
44201407	CLASS C PATCHES, TYPE III, 14 INCH	SQ YD	224	224
48101200	AGGREGATE SHOULDERS, TYPE B	TON	268	268
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	268	268
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1



△ REVISED 12-31-2024

REV - MS

MODEL - SUMMARY OF QUANTITIES (Sheet)
FILE NAME - c:\pwr_work\pwr\illinois.gov\alexis.hall2\illinois.gov\alexis.hall2\illinois.gov\alexis.hall2\ShtC-SqO.dgn

USER NAME = Alexis.Hall2	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
	CHECKED -	REVISED -	
PLOT DATE = 10/2/2024	DATE -	REVISED -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	102RS-5	PERRY	12	5
CONTRACT NO. 78A68				
ILLINOIS FED. AID PROJECT				