



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 6, 2024

SUBJECT FAP Route 303 (IL 173)
Project NHPP-5NDC(434)
Section FAP 0303 22 RS
McHenry County
Contract No. 62R95

Item No. 51, January 17th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices of the Plans.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Added page 24A to the Special Provisions.
4. Revised sheets 3 and 5 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
STATUS OF UTILITIES (D1)	2
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1)7	
PUBLIC CONVENIENCE AND SAFETY (D1)	8
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	9
FRICTION AGGREGATE (D1)	16
GRADING AND SHAPING SHOULDERS (D1)	19
ENGINEER’S FIELD OFFICE TYPE A (D1).....	19
TRAFFIC CONTROL PLAN (D1)	20
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1).....	21
TEMPORARY INFORMATION SIGNING	22
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	23
CENTER LINE – RUMBLE STRIP	24
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	24A
45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING	25
AGGREGATE SUBGRADE IMPROVEMENT (BDE)	34
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	36
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	37
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE).....	39
COMPENSABLE DELAY COSTS (BDE).....	50
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	54
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	56
FUEL COST ADJUSTMENT (BDE).....	59
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	61
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	63
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	68
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	69
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	73
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	73
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	74
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	74
SUBMISSION OF PAYROLL RECORDS (BDE)	75



VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 76
WEEKLY DBE TRUCKING REPORTS (BDE)..... 77
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 77
WORKING DAYS (BDE) 79



REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Intersection of IL 173 and County Line Road, Harvard, McHenry County

- Station 21+80 to Station 23+00 (CL IL 173), 100 feet LT to 150 feet RT. All excavation planned for ADA ramp Improvements and shoulder rehabilitation and construction. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

East of the Intersection of IL 173 and County Line Road, Harvard, McHenry County

- Station 23+00 to Station 108+50 (CL IL 173), 20 feet LT to 20 feet RT. All excavation planned for shoulder rehabilitation and construction. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None