



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 19, 2024

SUBJECT FAP Route 365 (IL 56 (Butterfield Rd))
Project NHPP-KH8K(115)
Section FAP 0365 22 RS
DuPage County
Contract No. 62T21
Item No. 53, January 17, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 105 to the Special Provisions
4. Revised sheets 3, 5 & 15 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

| | |
|--|-----|
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... | 76 |
| SUBMISSION OF BIDDERS LIST INFORMATION (BDE)..... | 77 |
| SUBMISSION OF PAYROLL RECORDS (BDE)..... | 77 |
| TRAINING SPECIAL PROVISIONS (BDE)..... | 79 |
| IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION | 82 |
| VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)..... | 84 |
| WEEKLY DBE TRUCKING REPORTS (BDE) | 84 |
| WORK ZONE TRAFFIC CONTROL DEVICES (BDE) | 85 |
| WORKING DAYS (BDE) | 86 |
| PROJECT LABOR AGREEMENT..... | 87 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) | 105 |

Revised 12/19/2024

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Intersection of Butterfield Road (IL 56) and Twin Pines Drive, Warrenville, DuPage County

- All excavation planned at the northwest quadrant, north island, and northeast quadrant at the intersection of Butterfield Road (IL 56) and Twin Pines Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Butterfield Road (IL 56) and Rockwell Street, Warrenville, DuPage County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of Butterfield Road (IL 56) and Rockwell Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Butterfield Road (IL 56) and Danda Square East Shopping Center Entrance Drive, Warrenville, DuPage County

- All excavation planned at the northeast quadrant at the intersection of Butterfield Road (IL 56) and Danda Square East Shopping Center Entrance Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**

Added 12/19/2024