



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2024

SUBJECT FAP Route 333 (IL 120 / Belvidere Rd)
Project NHPP-D14I(309)
Section (12-B-1)BR 23
Lake County
Contract No. 62W32

Item No. 56, January 17th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices of the Plans.
2. Revised pages i of the Table of Contents of the Special Provisions.
3. Revised page 13 of the Special Provisions.
4. Revised sheets 1-3 of the Plans.
5. Add sheets 3A of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	5
TRAFFIC CONTROL PLAN (D1)	6
TEMPORARY INFORMATION SIGNING	7
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	8
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	9
WEED CONTROL, BROADLEAF WEED CONTROL	10
CONTRACTOR COOPERATION	11
EROSION CONTROL BLANKET, SPECIAL	12
WOOD FENCE TO BE REMOVED AND REPLACED	13
FENCE REMOVAL AND REINSTALLATION	13
404 PERMIT	14
IEPA 401 PERMIT-3	19
IEPA 401 PERMIT-14	25
NATIONWIDE PERMIT-SUMMARY-3	32
NATIONWIDE PERMIT-SUMMARY-14	46
COMPENSABLE DELAY COSTS (BDE)	60
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	63
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	65
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	68
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	70
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	73
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	74
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	74
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	75
SUBMISSION OF PAYROLL RECORDS (BDE)	75
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	76
WEEKLY DBE TRUCKING REPORTS (BDE)	77
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	77
WORKING DAYS (BDE)	79





WOOD FENCE TO BE REMOVED AND REPLACED

~~Description: This work shall consist of the complete removal and disposal of existing wooden fencing and the furnishing and installing of wood post and rail fence in accordance with applicable portions of Sections 507 and 641 of the Standard Specifications, at the location(s) shown on the plans.~~

~~The existing wooden fence, including rails, posts, concrete, and hardware, shall be completely removed, and disposed of by the Contractor.~~

~~General Requirements: The new wood fence posts and rails shall comply with the requirements of Section 1007 of the Standard Specifications for No. 1 Dense SR 1550 F for southern pine or No. 1 Dense 1400 F for Douglas fir. All lumber shall be sound and free from excessive splitting or deterioration. Dimensions shown on the plans are for surfaced (S4S) lumber. All wood used for posts and rails shall be treated with ACA or CCA according to Article 1007.12, Miscellaneous Lumber for Human Contact. After erection of the fence, the Contractor shall apply two (2) coats of a commercially available water seal for treated lumber meeting the approval of the Engineer. Hardware shall include all necessary fasteners and appurtenances for construction of the fence and shall be according to Article 1006.17.~~

~~Wooden fence construction shall conform to the applicable portions of Sections 507 and 641 of the Standard Specifications. The backfill for posts shall be CA 6, CA 10, or CA 12 aggregate according to Article 1004.01. Backfill shall be thoroughly compacted, meeting the approval of the Engineer~~

~~Method of Measurement: The wooden fence removal will be measured for payment in feet along the top of existing fence. The wood posts and rail fence will be measured for payment in feet along the top of the fence from center to center of end posts.~~

~~Basis of Payment: The removal of the wooden fence shall be paid for at the contract unit price per foot for WOODEN FENCE REMOVAL. The new wood fence will be paid for at the contract unit price per foot for WOOD POST AND RAIL FENCE.~~

FENCE REMOVAL AND REINSTALLATION

Description: This work shall consist of removing, storing and re-erecting the fence, gates and accessories as directed by the Engineer.

The Contractor shall remove, store, protect, and reinstall the existing wood fence in a workmanlike manner to avoid damaging the material. Any repair or touch-up required shall be performed by the Contractor using a method approved by the Engineer, at no additional cost. If any material is damaged by the Contractor, it shall be replaced with the same type of material at no additional cost.

The existing wood fence shall be removed to the nearest post location as directed by the Engineer. If the existing posts are set in concrete foundations, the Contractor shall remove the posts from the foundations. The existing foundations shall be disposed of by the Contractor in accordance with Article 202.03 of the Standard Specifications. The resultant voids at the removal locations shall be backfilled with controlled low strength material or topsoil as directed by the Engineer.

The proposed post foundations shall be constructed to match the existing post foundations or as otherwise directed by the Engineer.

Method of Measurement: The wooden fence removal will be measured for payment in feet along the top of existing fence.

Basis of Payment: This work will be paid for at the contract unit price per foot for FENCE REMOVAL AND REINSTALLATION.

Revised 1/8/2025