



Illinois Department of Transportation

Office of Intermodal Project Implementation / Division of Aeronautics
1 Langhorne Bond Drive / Springfield, Illinois 62707-8415

January 10, 2025

SUBJECT: Kewanee Municipal Airport
Kewanee, Illinois
Henry County
Illinois Project Number: EZI-4939
SBG Project Number: 3-17-SBGP-TBD
Contract No. KE020
Item No. 06A, January 17, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS

Below is a clarification regarding requirements for 610 concrete.

610 concrete is specified as incidental concrete for base mounted lights. As a supplement to the specifications the below further clarifies the requirements for this material and its approval.

For concrete mix approval the contractor must submit an IDOT approved highways SI mix with a strength history.

A QC Plan will also be required which will need to include:

- Approved IDOT QC Plan (including personnel with certifications and Level 2 contact name and number)
- Lab Approval
- Plant Approval
- Plant Calibrations (include scale weight testing data)

All of these items should be available from the plant as part of a prior IDOT approval process.

During construction, production testing is required that includes cylinders, slump, temperature and air content on each day of production at a frequency of 1 test per 100 cubic yards.

In addition, pre-cast base cans from an IDOT approved pre-caster may be utilized.

Prime contractors must utilize the above material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Questions on this addendum may be directed to Lindsay Hausman of Hanson Professional Services Inc. at 217.747.9314.