

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	2006-007 I	KANE & KENDALL	38	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE SFTY-2A		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOC 1	LOC 2
			100% STATE	047-0006 KENDALL CO	045-0039 KANE CO
28100107	STONE RIPRAP, CLASS A4	SO YD	40.4		40.4
28200200	FILTER FABRIC	SO YD	63.6		63.6
50800515	BAR SPLICERS	EACH	24	24	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3030	3030	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18.3	18.3	
50102400	CONCRETE REMOVAL	CU YD	18.3	18.3	
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	135	135	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CALMO	3	1	2
67100100	MOBILIZATION	L SUM	1	0.25	0.75
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.50	0.50
*81800340	AERIAL CABLE, 3-1/C NO. 8 WITH MESSENGER WIRE	FOOT	40		40
70400100	TEMPORARY CONCRETE BARRIER	FOOT	250	250	△
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	150	150	
*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	30		30
*89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	30		30
X0320887	POLYMER CONCRETE	CU FT	32.2	16.0	16.2
X0321744	SILICONE JOINT SEALER, 2"	FOOT	597.6	401.6	196
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SO FT	144	48	96

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE SFTY-2A		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOC 1	LOC 2
			100% STATE	047-0006 KENDALL CO	045-0039 KANE CO
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	63.3		63.3
*X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	1		1
*X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	30		30
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	70.2		70.2
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	1743.1		1743.1
*X8110145	CONDUIT ATTACHED TO STRUCTURE, 1" DIA. RIGID GALVANIZED STEEL, PVC COATED	FOOT	30		30
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1		1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	12		12
*X0325906	ELECTRIC CABLE IN CONDUIT, (EPR-TYPE RHW), 3-1/C NO. 10, 1/C NO. 10 GROUND	FOOT	32		32
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	

△ Rev. 1-2-08

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

11/5/2007