

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2007-056 SG	COOK	30	2
STA. 28+00		TO STA.35+00		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND COMMITMENTS
- 3 SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5 ALIGNMENT, TIES, AND BENCHMARKS
- 6 REMOVAL PLANS
- 7 SIGNING FRAME PLAN
- 8-11 STAGES OF CONSTRUCTION AND TRAFFIC CONTROL SHEETS
- 12-24 SIGNING PLANS
- 25-26 **NOT USED**
- 27 FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAIL (TC-8)
- 28-29 MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
- 30 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES (TC-17)

GENERAL NOTES

1. EARTH EXCAVATION, FURNISHED EXCAVATION AND REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR THE ITEM OF WORK FOR WHICH IT IS REQUIRED.
2. TIE BARS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST FOR COMBINATION CONCRETE CURB AND GUTTER, TYPE AS SPECIFIED.
3. OVERHEAD STRUCTURES HAVE NOT BE SHOWN FOR PLAN CLARITY. THE CONTRACTOR SHALL VERIFY THAT ALL EQUIPMENT IS CAPABLE OF OPERATING AT THE SITE PRIOR TO BIDDING.
4. PRIOR TO REMOVAL, CURB AND GUTTER AND PAVEMENT TO BE REMOVED SHALL BE SAW CUT ALONG ANY EDGE WHERE EXISTING PAVEMENT OR CURB AND GUTTER SHALL REMAIN. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE APPROPRIATE ITEM OF REMOVAL.
5. BITUMINOUS AND AGGREGATE PRIME COAT SHALL BE APPLIED IN ACCORDANCE WITH SECTION 406 OF THE STANDARD SPECIFICATIONS. THE COST OF THE PRIME COATS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER TON FOR HOT-MIX ASPHALT SURFACE COURSE OF THE TYPE SPECIFIED.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

MIXTURE TYPE	AC TYPE	AIR VOIDS
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (IL 9.5mm); 4"	PG 64-22	4% @ 50 Gyr.
HMA SHOULDER (HMA BINDER IL-19mm); 14"	PG 64-22*	4% @ 70 Gyr.
HMA SHOULDER (HMA BINDER IL-19MM); 6"	PG 64-22*	4% @ 70 Gyr.

THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX ASPHALT SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

* WHEN RAP EXCEEDS 20%, THE NEW ASPHALT BINDER IN THE MIX SHALL BE PG 58-22.

HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-01 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 280001-04 TEMPORARY EROSION CONTROL SYSTEMS
- 606001-03 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 630001-07 STEEL PLATE BEAM GUARDRAIL
- 630301-04 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
- 631031-06 TRAFFIC BARRIER TERMINAL, TYPE 6
- 635001 DELINEATORS
- 635006-02 REFLECTOR AND TERMINAL MARKER PLACEMENT
- 635011-01 REFLECTOR MARKER AND MOUNTING DETAILS
- 701400-02 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401-04 LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701402-06 LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
- 701411-04 LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS >= 45 MPH
- 701446 TWO LANE CLOSURE FREEWAY/EXPRESSWAY
- 701901 TRAFFIC CONTROL DEVICES
- 704001-04 TEMPORARY CONCRETE BARRIER
- 780001-01 TYPICAL PAVEMENT MARKINGS
- 781001-02 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

PLAN

DATE: _____ BY: _____

SURVEYED _____

ALIGNED _____

NOTED _____

RT. OF WAY CHECKED _____

PAID FILE NAME _____

NOTE BOOK NO. _____

PROFILE

DATE: _____ BY: _____

SURVEYED _____

GRADES CHECKED _____

NOTED _____

STRUCTURE NOTATIONS "CHD" _____

NOTE BOOK NO. _____

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 INDEX OF SHEETS, LIST OF ILLINOIS
 DOT HIGHWAY STANDARDS, GENERAL
 NOTES, COMMITMENTS
 1-90/94 (KENNEDY EXPRESSWAY)

SCALE: VERT. 1:20
 HORIZ. 1:20
 DATE 10/31/07
 DRAWN BY: DLZ
 CHECKED BY: GB

Rev. 1-3-08

