

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2007-056 SG	COOK	30	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

PLAN	STARTED	DATE
	BY	
	NOTED	
	BY	
	DATE	
	NO.	

PROFILE	STARTED	DATE
	BY	
	NOTED	
	BY	
	DATE	
	NO.	

70300550 PAVEMENT MARKING TAPE, TYPE III 8"

FOOT	LOCATION
223	STA 29+31.3 TO STA 31+52.4
347	STA 29+31.3 TO STA 32+75.7
347	STA 29+31.3 TO STA 32+75.7
917	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
149	STA 29+31.3 TO STA 31+52.4 8"
231	STA 29+31.3 TO STA 32+75.7 8"
231	STA 29+31.3 TO STA 32+75.7 8"
611	TOTAL

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
248	STA 31+65.6 TO STA 34+13.4
29	STA 36+93.2 TO STA 38+10.0 2' DASH/6' SKIP
268	STA 40+92.1 TO STA 43+59.6
545	TOTAL

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION
266	STA 29+31.3 TO STA 31+95.5
43	STA 31+52.4 TO STA 31+95.5
346	STA 29+31.3 TO STA 32+75.7
347	STA 29+31.3 TO STA 32+75.7
1002	TOTAL

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION
43	STA 29+67.1 GORE MARKING
40	STA 29+95.7 GORE MARKING
36	STA 30+24.2 GORE MARKING
31	STA 30+52.8 GORE MARKING
25	STA 30+81.3 GORE MARKING
19	STA 31+09.8 GORE MARKING
12	STA 31+38.4 GORE MARKING
6	STA 31+66.9 GORE MARKING
212	TOTAL

78003120 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"

FOOT	LOCATION
250	STA 36+42.7 TO STA 46+57.1 10' DASH/30' SKIP
250	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
13	STA 31+65.6 TO STA 33+16.7 2' DASH/6' SKIP 4"
64	STA 33+16.7 TO STA 34+13.4 8"
106	STA 36+42.7 TO STA 46+57.1 10' DASH/30' SKIP 5"
10	STA 36+93.2 TO STA 38+10 2' DASH/6' SKIP 4"
13	STA 40+92.1 TO STA 42+47.4 2' DASH/6' SKIP 4"
75	STA 42+47.4 TO STA 43+59.6 8"
82	STA 31+65.6 TO STA 34+11.8 4"
65	STA 33+16.7 TO STA 34+13.9 8"
3	STA 33+41.2 GORE MARKING 12"
6	STA 33+71.8 GORE MARKING 12"
10	STA 34+02.3 GORE MARKING 12"
81	STA 40+92.1 TO STA 43+33.2 4"
57	STA 42+47.4 TO STA 43+33.4 8"
2	STA 42+61.9 GORE MARKING 12"
6	STA 42+91.7 GORE MARKING 12"
10	STA 43+21.9 GORE MARKING 12"
177	STA 29+31.3 TO STA 31+95.5 8"
29	STA 31+52.4 TO STA 31+95.5 8"
231	STA 29+31.3 TO STA 32+75.7 8"
231	STA 29+31.3 TO STA 32+75.7 8"
43	STA 29+67.1 GORE MARKING 12"
40	STA 29+95.7 GORE MARKING 12"
36	STA 30+24.2 GORE MARKING 12"
31	STA 30+52.8 GORE MARKING 12"
25	STA 30+81.3 GORE MARKING 12"
19	STA 31+09.8 GORE MARKING 12"
12	STA 31+38.4 GORE MARKING 12"
6	STA 31+66.9 GORE MARKING 12"
1483	TOTAL



1 ADDENDUM 1 - 1-3-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 I-90/94 (KENNEDY EXPRESSWAY)

SCALE: VERT. 1:20  
 HORIZ. 1:20  
 DATE 10/31/07  
 DRAWN BY: DLZ  
 CHECKED BY: GB

