

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2007-056 SG	COOK	30	4
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

PLAN	DATE	BY
SAVED		
ALIGNMENT CHECKED		
NOTE BOOK NO.		
CAD FILE NAME		

PROFILE	DATE	BY
SAVED		
REVISIONS CHECKED		
NOTE BOOK NO.		
CAD FILE NAME		

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION
1087	STA 25+54.8 TO STA 36+42.6
280	STA 36+42.6 TO RAMP E
176	STA 37+45.8 TO RAMP E
912	STA 37+45.8 TO STA 46+57.0
214	STA 46+57.0 TO STA RAMP 0
2669	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
363	STA 25+54.8 TO STA 36+42.6 4"
93	STA 36+42.6 TO RAMP E 4"
59	STA 37+45.8 TO RAMP E 4"
304	STA 37+45.8 TO STA 46+57.0 4"
71	STA 46+57.0 TO STA RAMP 0 4"
890	TOTAL

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
248	STA 31+65.6 TO STA 34+13.4
29	STA 36+93.2 TO STA 38+10.0 2' DASH/6' SKIP
268	STA 40+92.1 TO STA 43+59.6
545	TOTAL

78003120 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"

FOOT	LOCATION
250	STA 36+42.7 TO STA 46+57.1 10' DASH/30' SKIP
250	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
13	STA 31+65.6 TO STA 33+16.7 2' DASH/6' SKIP 4"
64	STA 33+16.7 TO STA 34+13.4 8"
106	STA 36+42.7 TO STA 46+57.1 10' DASH/30' SKIP 5"
10	STA 36+93.2 TO STA 38+10 2' DASH/6' SKIP 4"
13	STA 40+92.1 TO STA 42+47.4 2' DASH/6' SKIP 4"
75	STA 42+47.4 TO STA 43+59.6 8"
82	STA 31+65.6 TO STA 34+11.8 4"
65	STA 33+16.7 TO STA 34+13.9 8"
3	STA 33+41.2 GORE MARKING 12"
6	STA 33+71.8 GORE MARKING 12"
10	STA 34+02.3 GORE MARKING 12"
81	STA 40+92.1 TO STA 43+33.2 4"
57	STA 42+47.4 TO STA 43+33.4 8"
2	STA 42+61.9 GORE MARKING 12"
6	STA 42+91.7 GORE MARKING 12"
10	STA 43+21.9 GORE MARKING 12"
603	TOTAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 I-90/94 (KENNEDY EXPRESSWAY)

SCALE: VERT. 1:20  
 HORIZ. 1:20  
 DATE 10/31/07

DRAWN BY: DLZ  
 CHECKED BY: GB

