

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	SIGNAL Y031-1F			
* X0325890	REOPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL I	EACH	1		1			
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25				
20100410	TREE REMOVAL, SPECIAL (OVER 15 UNITS DIAMETER)	UNIT	44	44				
20101100	TREE TRUNK PROTECTION	EACH	7	7				
20200100	EARTH EXCAVATION	CU YD	3718	3718				
* 20200200	ROCK EXCAVATION	CU YD	450	450				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	24	24				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3016	3016				
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	120	120				
20800150	TRENCH BACKFILL	CU YD	1450	1450				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8396	8396				
25000210	SEEDING, CLASS 2A	ACRE	2	2				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180				
25100630	EROSION CONTROL BLANKET	SQ YD	8396	8396				
25200200	SUPPLEMENTAL WATERING	UNIT	84	84				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	180	180				
28000300	TEMPORARY DITCH CHECKS	EACH	20	20				
28000400	PERIMETER EROSION BARRIER	FOOT	4500	4500				
28000510	INLET FILTERS	EACH	26	26				
28100105	STONE RIPRAP, CLASS A3	SQ YD	712	712				
28200200	FILTER FABRIC	SQ YD	712	712				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2200	2200				
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	715	715				
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	3600	3600				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	270	270				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	285	285				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	SIGNAL Y031-1F			
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7				
40600300	AGGREGATE (PRIME COAT)	TON	33	33				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1005	1005				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84	84				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	180	180				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	63	63				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1848	1848				
42001300	PROTECTIVE COAT	SQ YD	4406	4406				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4345	4345				
42400800	DETECTABLE WARNINGS	SQ FT	54	54				
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	10700	10700				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	530	530				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3005	3005				
44000600	SIDEWALK REMOVAL	SQ FT	5275	5275				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	400	400				
44003100	MEDIAN REMOVAL	SQ FT	7770	7770				
44004250	PAVED SHOULDER REMOVAL	SQ YD	1305	1305				
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	200	200				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	200	200				
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	70	70				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	70	70				
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	70	70				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	70	70				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10700	10700				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	714	714				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1098	1098				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. 1-7-08