

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	SIGNAL Y031-1F		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	50	50			
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	750	750			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	282	282			
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	490	490			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	872	872			
60107600	PIPE UNDERDRAINS 4"	FOOT	500	500			
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	7	7			△
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			△
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	2	2			
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4			△
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	3	3			
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	5	5			△
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6			
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3			
60500050	REMOVING CATCH BASINS	EACH	4	4			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5	5			
60600105	CONCRETE CURB	FOOT	83	83			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3548	3548			
60623711	CONCRETE MEDIAN	SQ FT	380	380			
60624600	CORRUGATED MEDIAN	SQ FT	110	110			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	75	75			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	75	75			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	SIGNAL Y031-1F		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL OR	5	5			△
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5370	5370			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11200	11200			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1020	1020			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	550	550			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7040	7040			
* 72000200	SIGN PANEL - TYPE 2	SQ FT	52				52
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11200	11200			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1020	1020			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	190	190			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	150	150			
81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	105				105
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	765				765
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	130				130
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10				10
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	316				316
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	385				385

\* SPECIALTY ITEMS  
NP = NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev. 1-7-08

Rev.

PLOT DATE: 10/31/2007

10/31/2007