

20200100	EARTH EXCAVATION					
	CU YD	LOCATION				
	149	IL 40	243+50	-	252+ 00	
	149	LT & RT				
		TOTAL				
20400800	FURNISHED EXCAVATION					
	CU YD	LOCATION				
	505	IL 40	243+50	-	252+ 00	
	505	LT & RT				
		TOTAL				
25100630	EROSION CONTROL BLANKET					
	SQ YD	LOCATION				
	700	IL 40	243+50	-	247+ 40	
	231	RT	244+90	-	247+ 40	
	640	LT	248+02	-	250+ 25	
	643	RT	248+09	-	251+ 79	
	2,214	LT				
		TOTAL				
28000400	PERIMETER EROSION BARRIER					
	FOOT	LOCATION				
	390	IL 40	243+50	-	247+ 40	
	250	RT	244+90	-	247+ 40	
	223	LT	248+02	-	250+ 25	
	370	RT	248+09	-	251+ 79	
	1,233	LT				
		TOTAL				
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A					
	TON	LOCATION				
	113.47	IL 40	245+85.77	-	249+ 59.38	STAGE 1 - TEMP PAVEMENT
	113.47	RT				
		TOTAL				
40600625	LEVELING BINDER (MACHINE METHOD), N50					
	TON	LOCATION				
	15.55	IL 40	246+39.02	-	247+ 39.04	
	15.55	STA	248+02.71	-	249+ 02.71	
	31.10	STA				
		TOTAL				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50					
	TON	LOCATION				
	56.21	IL 40	243+54.27	-	247+ 39.07	SHOULDER
	32.03	RT	244+89.42	-	247+ 38.99	SHOULDER
	23.50	LT	246+39.02	-	247+ 39.04	MAINLINE
	28.51	STA	248+02.48	-	250+ 15.56	SHOULDER
	47.73	RT	248+02.77	-	251+ 79.15	SHOULDER
	23.42	LT	248+02.71	-	249+ 02.72	MAINLINE
	211.40	STA				
		TOTAL				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"					
	SQ YD	LOCATION				
	279.82	IL 40	246+39.04	-	247+ 39.04	
	278.86	STA	248+02.71	-	249+ 02.72	
	558.68	STA				
		TOTAL				

48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"					
	SQ YD	LOCATION				
	401.47	IL 40	243+54.27	-	247+ 39.07	
	228.79	RT	244+89.42	-	247+ 38.99	
	203.65	LT	248+02.48	-	250+ 15.56	
	340.94	RT	248+02.77	-	251+ 79.15	
	1174.85	LT				
		TOTAL				
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A					
	FOOT	LOCATION				
	275.00	IL 40	244+04.27	-	246+ 73.68	
	100.00	RT	245+73.38	-	246+ 73.38	
	50.00	LT	248+69.70	-	249+ 19.71	
	212.50	RT	248+69.60	-	250+ 82.09	
	637.50	LT				
		TOTAL				
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A					
	EACH	LOCATION				
	1	IL 40	246+73.68	-	247+ 19.39	
	1	RT	246+73.38	-	247+ 19.54	
	1	LT	248+24.01	-	248+ 69.70	
	1	RT	248+23.88	-	248+ 69.60	
	4	LT				
		TOTAL				
63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)					
	EACH	LOCATION				
	1	IL 40	243+54.28	-	244+ 04.27	
	1	RT	245+23.38	-	245+ 73.38	
	1	LT	249+19.71	-	249+ 69.71	
	1	RT	250+82.09	-	251+ 32.09	
	4	LT				
		TOTAL				
63200310	GUARDRAIL REMOVAL					
	FOOT	LOCATION				
	723	IL 40	243+54.27	-	250+ 77.26	
	810	RT	244+91.41	-	253+ 00.60	
	1533	LT				
		TOTAL				
63500105	DELINEATORS					
	EACH	LOCATION				
	1	IL 40	243+48.73	-	245+ 23.38	
	1	RT	249+69.71	-	251+ 32.09	
	1	LT				
	4	LT				
		TOTAL				
70106700	TEMPORARY RUMPLE STRIP					
	EACH	LOCATION				
	1	IL 40	226+70.86	-	231+ 70.86	
	1	RT	236+70.88	-	258+ 22.22	
	1	LT	263+22.22	-	268+ 22.22	
	1	RT				
	6	LT				
		TOTAL				