

70300520 PAVEMENT MARKING TAPE TYPE III, 4"

| EQOT     | LOCATION |           |   |            |                  |
|----------|----------|-----------|---|------------|------------------|
|          | IL 40    |           |   |            |                  |
| 672.74   | RT       | 243+87.47 | - | 250+ 60.21 | STAGE II (WHITE) |
| 381.20   | LT       | 245+62.39 | - | 249+ 43.59 | STAGE II (WHITE) |
| 553.49   | LT       | 245+24.66 | - | 250+ 78.15 | STAGE I (WHITE)  |
| 353.63   | RT       | 245+95.77 | - | 249+ 49.40 | STAGE I (WHITE)  |
| 1,961.06 | TOTAL    |           |   |            |                  |

70300570 PAVEMENT MARKING TAPE TYPE III, 24"

| EQOT | LOCATION |           |  |  |                            |
|------|----------|-----------|--|--|----------------------------|
|      | IL 40    |           |  |  |                            |
| 12   | RT       | 243+70.86 |  |  | STOP BAR, STAGE II (WHITE) |
| 12   | RT       | 245+60.04 |  |  | STOP BAR, STAGE I (WHITE)  |
| 12   | LT       | 250+39.91 |  |  | STOP BAR, STAGE I (WHITE)  |
| 12   | LT       | 251+22.22 |  |  | STOP BAR, STAGE II (WHITE) |
| 48   | TOTAL    |           |  |  |                            |

70301000 WORKZONE PAVEMENT MARKING REMOVAL

| SQ. FT. | LOCATION |           |   |            |                            |
|---------|----------|-----------|---|------------|----------------------------|
|         | IL 40    |           |   |            |                            |
| 24.00   | RT       | 243+70.86 |   |            | STOP BAR, STAGE II (WHITE) |
| 223.95  | RT       | 243+87.47 | - | 250+ 60.21 | STAGE II (WHITE)           |
| 24.00   | RT       | 245+60.04 |   |            | STOP BAR, STAGE I (WHITE)  |
| 184.31  | LT       | 245+24.66 | - | 250+ 78.15 | STAGE I (WHITE)            |
| 126.94  | LT       | 245+62.39 | - | 249+ 43.59 | STAGE II (WHITE)           |
| 117.76  | RT       | 245+95.77 | - | 249+ 49.40 | STAGE I (WHITE)            |
| 24.00   | LT       | 250+39.91 |   |            | STOP BAR, STAGE I (WHITE)  |
| 24.00   | LT       | 251+22.22 |   |            | STOP BAR, STAGE II (WHITE) |
| 748.96  | TOTAL    |           |   |            |                            |

70400100 TEMPORARY CONCRETE BARRIER

| EQOT | LOCATION |           |   |            |          |
|------|----------|-----------|---|------------|----------|
|      | IL 40    |           |   |            |          |
| 38   | RT       | 245+96.18 | - | 246+ 34.19 | STAGE II |
| 275  | LT       | 246+34.19 | - | 249+ 08.21 | STAGE I  |
| 38   | RT       | 249+08.21 | - | 249+ 45.73 | STAGE II |
| 350  | TOTAL    |           |   |            |          |

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

| EQOT | LOCATION |           |   |            |          |
|------|----------|-----------|---|------------|----------|
|      | IL 40    |           |   |            |          |
| 350  | RT       | 245+96.18 | - | 249+ 45.73 | STAGE II |
| 350  | TOTAL    |           |   |            |          |

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

| EQOT | LOCATION |         |   |         |                    |
|------|----------|---------|---|---------|--------------------|
|      | IL 40    |         |   |         |                    |
| 500  | STA.     | 242+ 50 | - | 252+ 50 | (YELLOW SKIP DASH) |
| 2000 | RT STA   | 242+ 50 | - | 252+ 50 | (WHITE EDGE LINE)  |
| 2000 | LT STA   | 242+ 50 | - | 252+ 50 | (WHITE EDGE LINE)  |
| 4500 | TOTAL    |         |   |         |                    |

78200410 GUARDRAIL MARKERS, TYPE A

| EACH | LOCATION |            |   |            |  |
|------|----------|------------|---|------------|--|
|      | IL 40    |            |   |            |  |
| 4    | RT       | 243+ 48.73 | - | 247+ 19.39 |  |
| 4    | LT       | 245+ 23.38 | - | 247+ 19.54 |  |
| 4    | RT       | 248+ 24.01 | - | 249+ 69.71 |  |
| 4    | LT       | 248+ 23.88 | - | 251+ 32.09 |  |
| 16   | TOTAL    |            |   |            |  |

78201000 TERMINAL MARKER - DIRECT APPLIED

| EACH | LOCATION |            |  |  |  |
|------|----------|------------|--|--|--|
|      | IL 40    |            |  |  |  |
| 1    | RT       | 243+ 48.73 |  |  |  |
| 1    | LT       | 245+ 23.38 |  |  |  |
| 1    | RT       | 249+ 69.71 |  |  |  |
| 1    | LT       | 251+ 32.09 |  |  |  |
| 4    | TOTAL    |            |  |  |  |

78300100 PAVEMENT MARKING REMOVAL

| SQ. FT. | LOCATION |            |   |            |                       |
|---------|----------|------------|---|------------|-----------------------|
|         | IL 40    |            |   |            |                       |
| 89.17   | STA.     | 243+ 70.86 | - | 244+ 60.03 | CENTERLINE - STAGE II |
| 633.88  | STA.     | 244+ 60.03 | - | 250+ 93.91 | CENTERLINE - STAGE I  |
| 28.31   | STA.     | 250+ 93.91 | - | 251+ 22.22 | CENTERLINE - STAGE II |
| 751.36  | TOTAL    |            |   |            |                       |

X0712400 TEMPORARY PAVEMENT

| SQ. YD | LOCATION |            |   |            |                         |
|--------|----------|------------|---|------------|-------------------------|
|        | IL 40    |            |   |            |                         |
| 166.05 | RT       | 245+ 85.77 | - | 249+ 59.38 | STAGE 1 - TEMP PAVEMENT |
| 166.05 | TOTAL    |            |   |            |                         |

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

| EACH | LOCATION |            |  |  |         |
|------|----------|------------|--|--|---------|
|      | IL 40    |            |  |  |         |
| 1    | LT       | 246+ 34.19 |  |  | STAGE I |
| 1    | LT       | 249+ 08.21 |  |  | STAGE I |
| 2    | TOTAL    |            |  |  |         |

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

| EACH | LOCATION |            |  |  |          |
|------|----------|------------|--|--|----------|
|      | IL 40    |            |  |  |          |
| 1    | RT       | 245+ 96.18 |  |  | STAGE II |
| 1    | RT       | 249+ 45.73 |  |  | STAGE II |
| 2    | TOTAL    |            |  |  |          |