

90% FED. 80% FED. 90% FED.  
10% ST. 20% ST. 10% ST.  
ACIM BRI ACIM

90% FED. 80% FED. 90% FED.  
10% ST. 20% ST. 10% ST.  
ACIM

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	ROADWAY J000-2A LASALLE	BRIDGE LASALLE	LIGHTING Y030-1E LASALLE
63200310	GUARDRAIL REMOVAL	FOOT	1,149	1,149		
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	266	266		
63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4		
63500105	DELINEATORS	EACH	170	170		
64200105	SHOULDER RUMBLE STRIP	FOOT	25,961	25,961		
66500105	WOVEN WIRE FENCE, 4'	FOOT	1,710	1,710		
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	1,215	1,215		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	29	29		
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	3	3		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	20		
67100100	MOBILIZATION	L SUM	1	1		
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1		
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	18	18		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,523	6,523		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	115,361	115,361		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,811	1,811		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,467	2,467		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	369	369		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	125	125		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	44,884	44,884		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	13,750	13,750		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	12,180	12,180		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	99	99		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	5		
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	146	146		
* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	96	96		
* 72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	1,406	1,406		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	14,861	14,861		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	ROADWAY J000-2A LASALLE	BRIDGE LASALLE	LIGHTING Y030-1E LASALLE
72900200	METAL POST - TYPE B	FOOT	56	56		
73000100	WOOD SIGN SUPPORT	FOOT	959	959		
73400100	CONCRETE FOUNDATIONS	CU YD	32	32		
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	79	79		
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	28	28		
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3,410	3,410		
78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS & SYMBOLS	SQ FT	88	88		
78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	48,835	48,835		
78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	1,123	1,123		
78008340	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	FOOT	5,973	5,973		
78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	1,751	1,751		
78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	FOOT	72	72		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	457	457		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	14	14		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	22,588	22,588		
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	45			45
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	35			35
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	235			235
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	187			187
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	168			168
81300520	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 8" X 6"	EACH	2			2
81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	13,286			13,286
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	243			243
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	486			486
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4,314			4,314

△ REVISED 1/16/08

\* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)  
**SUMMARY OF QUANTITIES**  
 SCALE: NONE  
 DATE: 11/02/07  
 DRAWN BY: KM  
 CHECKED BY: SE