

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
				ROADWAY J000-2A LASALLE	BRIDGE LASALLE	LIGHTING Y030-1E LASALLE
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10,791			10,791
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	34			34
82500520	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 480VOLT	EACH	1			1
83052200	LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., 12 FT. MAST ARM	EACH	34			34
83057220	LIGHT POLE, WOOD, 40 FOOT, CLASS 4	EACH	7			7
83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	7			7
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	34			34
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	120			120
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	14			14
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	12			12
84200700	LIGHTING FOUNDATION REMOVAL	EACH	12			12
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18			18
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	160	160		
X0712400	TEMPORARY PAVEMENT	SQ YD	25,154	25,154		
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	18,314	18,314		
X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	3,812	3,812		
X8440102	RELOCATE EXISTING LUMINAIRE	EACH	7			7
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	52,543	52,543		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2	2		
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6	6		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	7	7		
Z000530	ANCHOR BOLTS, 1 1/4"	EACH	16		16	
#Z0076600	TRAINEES	Hour	2,500	2,500		

• SPECIALTY ITEM # Y080



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)
SUMMARY OF QUANTITIES
 SCALE: NONE
 DATE: 11/02/07
 DRAWN BY: KM
 CHECKED BY: SE